


15-145-20387-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pawnee County, Sec. 32 Twp. 23S Rge. 16W (EX (W)  
Location as "NE/CNW&SW" or footage from lines SE SE SW  
Lease Owner Voyager Petroleum, Kansas-Nebraska Nat Gas, Sterling  
Lease Name Wurm "B" #1 Well No. Drilling Co  
Office Address P. O. Box 129, Sterling, Kansas 67579  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 8, 1975 19  
Application for plugging filed May 8, 1975 19  
Application for plugging approved May 8, 1975 19  
Plugging commenced 11:00 AM, May 8, 1975 19  
Plugging completed 1:15 PM, May 8, 1975 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 1365' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	267'	None

RECEIVED  
STATE CORPORATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud. 5-13-75  
Halliburton spotted 50 sacks 50/50 Pozmix through open end D.P. at 400'. Mud to 240', spotted 25 sacks : 240', mud to 40', solid bridge and 10 sacks to surface, 2 sacks in Rathole.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sterling Drilling Company  
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE ss.  
F. A. Wuelner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuelner  
F. A. Wuelner, Secretary  
P. O. Box 129, Sterling, Kansas 67579  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 1975

Bernard Laudermilk  
Bernard Laudermilk, Notary Public.

My commission expires \_\_\_\_\_

**BERNARD LAUDERMILK—NOTARY PUBLIC**  
My Commission Expires Jan. 22, 1978

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

15-145-20387-0000

WELL LOG - - - - - WURM "B" #1  
Located: SE SE SW, Section 32-23S-16W, Pawnee County, Kansas

OWNER: Voyager Petroleum, Kansas-Nebraska Natural Gas, Sterling Drilling Co.  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 28, 1975  
COMPLETED: May 8, 1975

TOTAL DEPTH: 4365'

LOG		CASING RECORD
0 - 87	Sand	Ran 6 joints used 8 5/8" casing, 256.16' set at 267' K.B. with 225 sacks 60/40.
87 - 210	Shale and Sand Strngers.	Pozmix with 3% cc. Plug down at 5:30 PM, 4-28-75.
210 - 268	Shale and Sand	
268 - 670	Shale, Sand and Red Bed	
670 - 1064	Red Bed and Sand	
1064 - 1093	Anhydrite	
1093 - 2030	Shale and Shells	
2030 - 3175	Lime and Shale	
3175 - 3670	Lime	
3670 - 3785	Lime and Shale	
3785 - 4180	Lime	
4180 - 4250	Lime and Shale	
4250 - 4280	Lime and Chert	
4280 - 4365	Lime, Chert and Shale	Plugged.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 1 1975  
CONSERVATION DIVISION  
Topeka, Kansas