

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-20,168-000

LEASE NAME Berscheidt

WELL NUMBER 1

3300 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 32 TWP. 23S RGE. 16 (E or W)

COUNTY Pawnee

Date Well Completed 9/30/70

Plugging Commenced 3/22/89

Plugging Completed 3/24/89

AMENDED

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Leben Oil Corp.

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6566

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on n/a (date)

by n/a (KCC District Agent's Name).

Is ACO-1 filed? on old form if not, is well log attached? -

Producing Formation Miss Depth to Top 4182 Bottom 4198 1/2 T.D. 4475

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Miss	Gas	4182	98 1/2	8 5/8	250	-0-
				4 1/2	4468 1/2	2371

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged bottom with sand + 4 sxs cmt to 4130'. Shot 4 1/2" casing @ 2371'; set plug with 400# hulls, 10 gel + 50 sxs cmt. Surf plug = 10 gel, 100# hulls, + 120 sxs 60/40 poz w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P. O. Box 347, Chase, KS 67524

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Leben Oil Corp.

STATE OF Oklahoma COUNTY OF Tulsa, ss.

APR 23 1989  
4-13-89

Charlotte Van Valkenburg

(Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 10th day of April, 19 89

Brenda K. Bowdee  
Notary Public

My Commission Expires: June 27, 1990

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-145-20,168-0000

LEASE NAME Berscheidt

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

         Ft. from S Section Line

         Ft. from E Section Line

LEASE OPERATOR Leben Oil Corporation

SEC. 32 TWP. 23 SRGE. 16 WXXXor(W)

ADDRESS P.O. Box 666  
Ellinwood, KS 67526

COUNTY Pawnee

PHONE (316) 564-3244 OPERATORS LICENSE NO. 6566

Date Well Completed         

Character of Well Oil

Plugging Commenced 3/22/89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3/24/89

The plugging proposal was approved on          (date)

by          (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4475'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	250	none
				4 1/2	4468 1/2	2371

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.  
Plugged bottom with sand to 4130', dumped 4 sacks cement, shot @2371',  
plugged surface with 400# hulls, 10 gel, 50 sacks cement, 10 gel, 100#  
hulls, 8 5/8" plug, 120 sacks 60/40 poz 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No.         

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Leben Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator Wichita, Kansas) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 28th day of March, 19 89

Irene Hoover  
Notary Public

My Commission Expires: 

WELL LOG

15-145-261 68.00000

Company Leben Drilling, Inc.

Sec. 32 T. 23S R. 16W

Contractor Leben Drilling, Inc.

Loc. C SE NE

Farm Berscheidt #1

County Pawnee

Total Depth 4475' RTD


Casing 8 5/8" New 20# Casing set @ 250' w/250 sxs. Common 2% C.C.

Commenced 9-17-70

Production

Completed 9-26-70

Producer



Figures Indicate Bottom of Formations

150	Sand
210	Sand & Shale
380	Shale
539	Red Bed
602	Sand
1059	Shale & Shells
1083	Anhydrite
1891	Shale & Shells
3852	Lime & Shale
4033	Lime
4145	Lime & Shale
4398	Lime & Chert
4475	Lime & Shale
<u>4475</u>	<u>RTD</u>

RECEIVED  
STATE CORPORATION COMMISSION


DEC 30 1968

CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas  
County of Barton

SS

I, James R. Rodgers of Leben Drilling, Inc., upon oath state that the above and foregoing is a true and correct copy of the log of the Berscheidt #1 Well.



James R. Rodgers

Subscribed and sworn to before me this 30th day of September, 1970

My Commission Expires: November 13, 1973

Helen L. Lindenmuth