

15-145-00148-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

Pawnee County, Sec. 32 Twp. 23 Rge. 16 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SW/4 SW/4 NW/4
Lease Owner Bell Oil and Gas Company
Lease Name Berscheidt Well No. 1
Office Address Box 2007, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-9 19 56
Application for plugging filed 11-9 19 56
Application for plugging approved 11-9 19 56
Plugging commenced 11-9 19 56
Plugging completed 11-9 19 56
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud to 240'. Set Halliburton plug, 1/2 sack hulls, pumped in 20 sacks of cement through drill pipe. Filled hole with heavy drilling mud to 35'. Set Halliburton plug, 1/2 sack hulls, cemented to bottom of cellar with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1956
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Transit Corporation
Address 1516 Liberty Bank Building, Oklahoma City 2, Oklahoma

STATE OF Oklahoma, COUNTY OF Oklahoma, ss.
C. W. Dodson (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Dodson
Oklahoma City, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 19 56
Carol Bradshaw
Notary Public.

My commission expires July 1, 1959

PLUGGING
FILE SEC 32 T. 23 R. 16W
BOOK PAGE 115 LINE 3

Bell Oil and Gas Company
Tulsa, Oklahoma
Berscheidt # 1

15-145-00148-0000

SW SW NW Section 32-23S-16W, Pawnee County, Kansas

Total Depth 4500' Elevation 2083' DF
Commenced 10-23-56 Casing: 8 5/8" @ 262'
Completed 11-9-56 200 sacks pozmix

<u>Formation</u>	<u>Depth</u>
Clay, sand, shale	225
Shale, Shells	385
Red bed	1073
Anhydrite	1090
Shale, Shells	1970
Shale, Lime	2215
Lime	2385
Lime, Shale	3030
Shale, Shells	3160
Lime, Shale	3740
Lime	3840
Lime, Chert	3938
Lime, Shale	4279
Lime	4337
Chert, Shale, Lime	4458
Lime	4500

I hereby certify the forgoing to be a true and correct Driller's Log to the best of my knowledge.

C. W. Dodson
C. W. Dodson

Subscribed and sworn to before me this 20th day of November, 1956.

My commission expires:
July 1, 1959

Carol Bradshaw
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

NOV 21 1956
PLUGGING
FILE SEC 32 T 23 R 16 W
BOOK PAGE 115 LINE 3
CONSERVATION DIVISION
Tulsa, Kansas