

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

15-145 20544.0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 34 Twp. 23S Rge. 16W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW SW SW

Lease Owner Zenith Drilling Corporation, Inc.
Lease Name Wurm #2 Well No. 2
Office Address Suite 600, 200 West Douglas, Wichita, Ks 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Dry Hole
Date Well completed May 4, 1979 19
Application for plugging filed May 4, 1979 19
Application for plugging approved May 4, 1979 19
Plugging commenced 9:00 AM - May 4, 1979 19
Plugging completed 11:30 AM - May 4, 1979 19
Reason for abandonment of well or producing formation

Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4180'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	254'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 600' with 70 sacks cement through drill pipe.
Heavy mud to 240' with 20 sacks cement through drill pipe.
Heavy mud to 40' with Howco plug, 1/4 sack hulls, solid bridge
and 10 sacks to surface. 3 sacks in rathole.
Used 50/50 Pozmix with 6% gel.

RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1979

(If additional description is necessary, use BACK of this sheet) 979
Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579
Conservation Division
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner
STERLING DRILLING COMPANY
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 79

My commission expires



Charles M. Hall
Charles M. Hall, Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-145-20594-0000

WELL LOG ----- WJRM #2
Located: NW SW SW, Section 34-23S-16W, Pawnee County,
Kansas

OWNER: Zenith Drilling Corporation, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 28, 1979
COMPLETED: May 4, 1979

TOTAL DEPTH: 4180'

LOG

CASING RECORD

0 - 100 Sand and Gravel
100 - 1048 Shale
1048 - 1068 Anhydrite
1068 - 1394 Shale
1394 - 4120 Lime and Shale
4120 - 4180 Lime

Ran 6 joints 8 5/8" casing. 241.24' set
at 254' K.B. Cemented with 225 sacks
60/40 Pozmix with 3% cc. Plug down at
3:30 PM, 4-28-79.

Plugged.

RECEIVED
STATE CORPORATION COMMISSION

MAY - 9 1979

CONSERVATION DIVISION
Topeka, Kansas