

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-145-70465-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 34 Twp. 23 Rge. 16 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW SW

Lease Owner Zenith Drilling Corporation
Lease Name Wurm Well No. 1
Office Address 505 Fourth Financial Center, Wichita,
Character of Well (Completed as Oil, Gas or Dry Hole) Kansas
oil 67202


Date Well completed April 27 19 77
Application for plugging filed Nov. 8 19 79
Application for plugging approved 19
Plugging commenced Nov. 29 19 79
Plugging completed Dec. 4 19 79

Reason for abandonment of well or producing formation
depleted

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4205'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Flat

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-------|--------|--------|------------|
| | | | 242' | 8 5/8" | 242' | none |
| | | | 4105' | 4 1/2" | 4105' | 2995.76 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3950' and dumped 4 sacks of cement.

Allied Cementing Company plugged well pumping in 6 sacks of hulls, 30 sacks of gel and 155 sacks of cement.

STATE RECEIVED
CORPORATION COMMISSION
DEC - 5 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GLENN'S CASING PULLING INC.
Box 413, Ellinwood, Kansas 67526

12-6-79

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December, 19 79

JENNY KASSELMAN
STATE NOTARY PUBLIC
Barton County, Kansas
My Appt. Exp. July 15, 1982

Jenny Kasselman
Notary Public.

My commission expires

DRILLER'S LOG

15-145-20465-000

ZENITH DRILLING CORPORATION
Wurm #1
NW SW
Section 34-23-16W
Pawnee County, Kansas
Elevation 2075 K.B.

COMM: 4-20-77
COMP: 4-27-77
CONTRACTOR: Sterling Drilling Co.
8 5/8" at 242' with 225 sacks
4 1/2" at 4105' with 125 sacks

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|---------------|-------|
| Shale & Lime | 3695' |
| Lime | 3971' |
| Shale & Lime | 4113' |
| Chert & Shale | 4148' |
| Shale | 4190' |
| Dolomite | 4205' |
| RTD | 4205' |

LOG TOPS

| | |
|--------------|--------------|
| Topeka | 3171 (-1096) |
| Heebner | 3571 (-1496) |
| Toronto | 3585 (-1510) |
| Douglas | 3603 (-1528) |
| Lansing | 3704 (-1629) |
| Base K. C. | 3971 (-1869) |
| Congl. Chert | 4113 (-2038) |
| Simpson | 4150 (-2075) |
| Arbuckle | 4196 (-2121) |
| RTD | 4205 |

RECEIVED
STATE CORPORATION COMMISSION
NOV 09 1979
CONSERVATION DIVISION
Wichita, Kansas

Sherrill Compton
Sherrill Compton - Geologist