

15-145-20442-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Pawnee SEC. 34 TWP. 23 RGE. 16W E/W  
 Location as in quarters or footage from lines:  
N/2 NW


Lease Owner Zenith Drilling Corporation  
 Lease Name George B-1 Well No.             
 Office Address Suite 505 Fourth Financial Center Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole):             
 Date Well Completed             
 Application for plugging filed             
 Plugging commenced            6-4-82  
 Plugging completed            7-13-82  
 Reason for abandonment of well or producing formation             
Depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation            Depth to top            bottom            T.D. 4145'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	253'	none
				4-1/2"	4144'	2570'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from            feet  
 to            feet for each plug set.

Plugged off bottom with sand to 4076' and ran 4 sacks cement. Shot casing @3010',  
2856', 2700' and 2580'. Pulled a total of 79 joints of 4-1/2" casing. Plugged well  
with 3 sacks hulls, 15 sacks gel, 70 sacks cement, 1 sack hulls, 10 sacks gel, released  
plug and displaced with 80 sacks 50/50 pos, 4% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso

Box 347 Chase, Ks. 67524

RECEIVED  
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 15th day of July, 19 82

JUL 16 1982

My Commission expires:           



Conservation Division  
 Wichita, Kansas

15-145 - 20442-0000

GEORGE B-1  
N/2 NW  
Sec. 34-23-16W  
Pawnee County, Kansas  
El. 2080 K.B.

Comm: 12-09-76  
Comp: 12-16-76  
Contractor: Sterling Drilling Co.  
8 5/8" at 253' with 225 sx  
4 1/2" at 4144 with 125 sx

DRILLER'S LOG

FORMATION TOPS:

Lansing	3696 (-1616)
Base K. C.	3962 (-1882)
Cong. Chert	4100 (-2020)
Arbuckle	4122 (-2042)
RTD	4145

8 5/8' at 253' with 225 sacks

4 1/2" (10 $\frac{1}{2}$ #) at 4144' with 125 sacks

Perforations at 4126-28, 4132-34, 4137-39

Cement bond log shows top of cement to be  
at 3500'.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1982

CONSERVATION DIVISION  
Wichita Kansas