

WELL PLUGGING RECORD

15-149-20973-000

Give All Information Completely
 Make Required Affidavit

COUNTY Pawnee SEC. 35 TWP. 23S RGE. 16W E/W
 Location as in quarters or footage from lines:
E235' FNL; 1235' FWL, NW/4

Lease Owner Sterling Drilling Company, et al
 Lease Name Schartz #2-35 Well No. 2-35
 Office Address P. O. Box 129, Sterling, Kansas 67579
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed June 10, 1982
 Application for plugging filed June 10, 1982
 Plugging commenced 6:30 AM, June 10, 1982
 Plugging completed 8:45 AM, June 10, 1982
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom T.D. 4240'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Filled hole with heavy mud.
Heavy mud to 720' with 70 sacks through open ended
drill pipe; heavy mud and 40 sacks at 300'; solid
bridge at 40', Howco plug and hulls; 10 sacks to
surface; 10 sacks in rathole and 5 sacks in mouse
hole. Used 50/50 Pozmix with 4% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
 (Signature) [Signature]
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas
 (Address) 67579

SUBSCRIBED AND SWORN TO before me this 11th day of June, 1982.



Agnes D. Wurst
 Notary Public.

My Commission expires: _____

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 14 1982
 CONSERVATION DIVISION
 Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

15.145.20973-0000

WELL LOG - - - - - SCHARTZ #2-35

Located: 1235' FNL; 1235' FWL, NW/4, Section 35-23S-16W,
Pawnee County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 2, 1982
COMPLETED: June 10, 1982

TOTAL DEPTH: 4240'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 41 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# OD casing. 262.41' pipe set at 276' K.B.
41 - 280 Sand and Shale	Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 7:45 PM, 6-2-82, by Howco.
280 - 1019 Shale	
1019 - 1040 Anhydrite	
1040 - 1270 Shale	
1270 - 4075 Lime and Shale	
4075 - 4200 Lime	
4200 - 4240 Lime, Chert	Plugged

Deviation Surveys: 1° at 1960'
2° at 4200'

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1982
CONSERVATION DIVISION
Wichita Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

15-145-26973-0000

WELL LOG - - - - - SCHARTZ #2-35

Located: 1235' FNL; 1235' FWL, NW/4, Section 35-23S-16W,
Pawnee County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 2, 1982
COMPLETED: June 10, 1982

TOTAL DEPTH: 4240'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 41 Surface Soil and Sand	Ran 6 joints 8 5/8", 24# OD casing.
41 - 280 Sand and Shale	262.41' pipe set at 276' K.B.
280 - 1019 Shale	Cemented with 225 sacks 60/40 Pozmix with 3% cc. Plug down at 7:45 PM, 6-2-82, by Howco.
1019 - 1040 Anhydrite	
1040 - 1270 Shale	
1270 - 4075 Lime and Shale	
4075 - 4200 Lime	
4200 - 4240 Lime, Chert	Plugged

Deviation Surveys: 1° at 1960'
2° at 4200'