

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 36 TWP. 23s RGE. 16W E/W
Location as in quarters or footage from lines:
C of W 1/2 NE SE

Lease Owner Messman-Rinehart Corporations
Lease Name Wiles Well No. #1
Office Address 1432 Vickers KSBT Bldg. Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole):
Date Well Completed
Application for plugging filed
Plugging commenced 11-13-81
Plugging completed 11-19-81
Reason for abandonment of well or producing formation

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4142'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	255'	none
				5-1/2"	4135'	2178'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3650' and set 5 sacks cement. Shot pipe @3325', 3000', 2815', 2685', 2595', 2495', 2400', 2270' and 2175'. Pulled a total of 68 joints of pipe. Plugged well with 15 sacks gel, 5 sacks hulls, 10 sacks gel, released plug, and displaced with 150 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 81

My Commission expires:



Irene Hoover
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1981

11-30-81
CONSERVATION DIVISION
Wichita Kansas

15-145-30087-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Lawrence SEC. 36 TWP. 23s RGE. 16W E/W
 Location as in quarters or footage from lines:
C of W 1/2 NE SW

Lease Owner Messman-Rinchart Corporations
 Lease Name Wiles Well No. 41
 Office Address 1432 Vickers KSBT Bldg. Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole):
 Date Well Completed
 Application for plugging filed
 Plugging commenced 11-13-81
 Plugging completed 11-19-81
 Reason for abandonment of well or producing formation

Locate Well
 correctly on above
 Section Platt.

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4142'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	255'	none
				5-1/2"	4135'	2175'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3650' and set 5 sacks cement. Shot pipe @3325', 3000', 2815', 2685', 2595', 2495', 2400', 2270' and 2175'. Pulled a total of 63 joints of pipe. Plugged well with 15 sacks gel, 5 sacks bulla, 10 sacks gel, released plug, and displaced with 150 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 81

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION
 Notary Public.
 DEC 21 1981

CONSERVATION DIVISION
 Wichita Kansas

COMPLETION DATA

Messman-Rinehart Oil Company
No. 1 Wiles
Ctr. W/2 NE/4 SE/4, Sec. 36-23S-16W
Pawnee County, Kansas

15-145-30087-0000

- 9/30/65 - Moved in cable tools, swabbed hole down to top of cement, drilled out cement
- 10/1/65 - Finished drilling out cement, loaded hole, drilled shoe, ran Lane-Wells Radioactivity Log, Set Baker Packer
- 10/2/65 - Perforated 4047-57 ft. w/4^S ft., Ran 2" tubing through packer to Arbuckle, Ran 1 $\frac{1}{4}$ " tubing to perforations
- 10/3/65 - Fraced w/15,000 sand and 16,000 gal. water, maximum pressure 2800#, broke to 2100# and fed in 4500# sand
- 10/4/65 - Swabbed through 1 $\frac{1}{4}$ " tubing
- 10/5/65 - Casing pressure 800#, well kicked off and flowed 4 hrs. (appears to be drying up)

Tested 2,196 Mcfg, 620# casing pressure (still a little moisture, to continue testing 10/7/65)

Pulled swab once and well kicked off from Arbuckle, making 4,000 Mcfg (dry) through 2" tubing

Waiting for gas connection

MESSMAN-RINEHART OIL COMPANY

By: 
Roger L. Messman

RLM/bjs
10/6/65

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1981

CONSERVATION DIVISION
Wichita, Kansas

Well Record:

Location: Ctr. W/2 NE/4 SE/4
 Section 36-23S-16W
 Pawnee County, Kansas

Contractor: Messman-Rinehart Oil Company
 1432 Wichita Plaza
 Wichita, Kansas, 67202

Operator: Messman-Rinehart Oil Company
 1432 Wichita Plaza
 Wichita, Kansas, 67202

Casing Record: 10-3/4" @ 255' w/125 sx. cement
 5-1/2" @ 4135' w/140 sx. cement

Commenced: May 31, 1965
 Completed: June 14, 1965
 (Rotary)
 Elevation: 2049' K/B
 Production: Gas

*** LOG ***

)Figures indicate bottom of formation)

Clay and Sand	90	
Shale & Sand Streaks	245	
Shale	255	
Shale & Red Bed	488	
Sand	570	
Shale	725	
Red Bed & Shells	980	
Anhydrite	1010	
Shale & Shells	1950	
Lime & Shale	2010	
Lime	2160	
Lime & Shale	2600	
Shale	2800	
Shale w/Lime Streaks	2970	
Shale & Lime	3140	
Lime & Shale	3320	
Lime	3433	
Lime & Shale	3650	
Lime	3745	
Lime (chalky)	3805	
Lime	4035	
Conglomerate	4060	
Lime - cherty	4095	
Conglomerate	4135	
Lime	4142 R.T.D.	

Samples - Top

980'	- Anhydrite (-1060)
3042'	- Howard (-993)
3511'	- Heebner (-1452)
3642'	- Brown Lime (-1593)
3652'	- Lansing (-1603)
3009'	- Conglomerate (-1960)
4132'	- Arbuckle (-2083)

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland
 J. A. Gilliland

Subscribed and sworn to before me this 7th day of July, 1965

Barbara J. Scott
 Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1968

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 21 1981
 CONSERVATION DIVISION
 Wichita, Kansas