

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-00523-0000

LEASE NAME Peters

WELL NUMBER #1

SPOT LOCATION SE SE NE

SEC. 36 TWP. 23S RGE. 16W (E) or (W)

COUNTY Pawnee

Date Well Completed _____

Plugging Commenced 9-19-86

Plugging Completed 10-6-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Messman-Rinehart Corporation

ADDRESS 500 Bitting Bldg. Wichita, Kansas 67202-1783

PHONE # (316) 263-4211 OPERATORS LICENSE NO. _____

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4130'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	245'	none
				5-1/2"	4130'	2176'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 3750' and 5 sacks cement. Shot pipe @2840', 2638', 2436', 2271', 2176', pulled a total of 68 joints of 5-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.


Mike Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

RECEIVED
Address P.O. Box 347 Chase, Ks. 67524

STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 86



Irene Hoover
Notary Public

My Commission expires: _____

OCT 8 1986