

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH

	X		

Locate well correctly on above
Section Plat

Finney County. Sec. 4 Twp. 21 Rge. (X) 32 (W)
Location as "NE/CNW/SW" or footage from lines C NE NW
Lease Owner Cities Service Oil Company
Lease Name HULLMAN "A" Well No. 1
Office Address 3545 N.W. 58th, Oklahoma City, Oklahoma 73112
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-31 1974
Application for plugging filed (Verbal) 12-30 1974
Application for plugging approved (Verbal) 12-30 1974
Plugging commenced 8:00 A.M., 12-31 1974
Plugging completed 10:00 A.M., 12-31 1974
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production N.A. 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation N.A. Depth to top --- Bottom --- Total Depth of Well 5190 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
N.A.				8-5/8"	1448	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran open ended drill pipe and spotted cement plugs as follows:

60 sacks cement from 689' to 550'
30 sacks cement from 395' to 500'
15 sacks cement from 4' to 45'
4 sacks cement in mouse & rat holes

The 8-5/8" csg. was cut off 4' below ground level and a steel cap with I.D. and date plate was welded on.

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1975

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF OKLAHOMA, COUNTY OF OKLAHOMA, ss.
I, H. E. Massey

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

H. E. Massey
Operations Manager

3545 N.W. 58th, Oklahoma City, OK 73112

(Address)

SUBSCRIBED AND SWORN to before me this 7th day of January, 1975

My commission expires

4/2/77

C. R. Paslay

Notary Public.

FORMATION, TESTING AND COMPLETION RECORD

Formation	Top	Bottom	Show Drill Stem Tests, Well Stimulation and Production Tests
Sand	0	240	Schlumberger Dual Induction Laterlog; Borehole Compensated Sonic w/Gamma Ray Caliper Log & Compensated Neutron For- mation Density Log from 5189' to 1448' and 1484' to 20'.
Shale	240	1015	
Sand & Shale	1015	1454	
Shale	1454	2200	
Lime & Shale	2200	3801	
Lime	3801	3865	
Lime & Shale	3865	4120	
Lime	4120	4195	
Lime & Shale	4195	4255	
Lime	4255	4690	
Lime & Shale	4690	4955	
Lime	4955	5190	
Rotary T.D.	5190		

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1975
CONSERVATION DIVISION
Wichita, Kansas