


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-149-20613-2000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Pawnee County. Sec. 18 Twp. 23S Rge. 16W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

_____ C of NW NE
Lease Owner D. R. Lauck Oil Co. Inc.
Lease Name Biryer-Schartz #1 Well No. _____
Office Address Box 488, Ellinwood, Ks. 67526
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-12-81 19____
Plugging completed 1-23-81 19____
Reason for abandonment of well or producing formation _____
Depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4159
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	359	None
				4-1/2	4153	2845'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeezed casing with 35 sacks cement. Pumped plug to 3800'. Made shots at 3845, 3420, 3220, 3020 and 2815. Pulled total of 85 joints. Allied pumped in 5 sacks hulls and 20 sacks gel. Stopped pumping as we were pumping gel out the rat hole. Ran 2" tubing into hole. Got to 420' and ran into a bridge. Couldn't wash the bridge out. Pumped in 160 sacks 50/50 pos and 4% gel. Didn't fill the hole up. Had Allied find top of cement which was at 86'. Ran tubing to top of cement. Pumped 60 sacks cement to top of surface. Squeezed 20 sacks cement outside of surface to fill up rat hole. Plugging complete.

RECEIVED

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING JAN 28 1981 1-28-81
CHASE, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of January, 1981

My commission expires



Joan Kelso
Notary Public.

15-145-20613-0000

D. R. Lauck Oil Company, Inc. -
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Birzer-Schartz #1
C NW NE Sec. 18-23S-16W
Pawnee County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: August 18, 1979
Completed: August 25, 1979

Drillers Log

Sand	110
Blue Shale	372
Red Bed	630
Shale	2540
Shale & Shells	3860
Shale & Lime	4085
Lime & Shale	4140
Lime	4159 RTD

RECEIVED
COMMISSION
NOV 17 1980
OPERATIONS DIVISION
Wichita, Kansas