


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 13 Twp. 21 Rge. 14 (X) (W)  
Location as "NE/CNW/SW" or footage from lines NW SW SE  
Lease Owner Petroleum, Inc. & Darrah-Garvin  
Lease Name McGINTY 'B' Well No. 1  
Office Address 311 East Third, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 21, 1954  
Application for plugging filed July 21, 1954  
Application for plugging approved July 21, 1954  
Plugging commenced July 21, 1954  
Plugging completed July 21, 1954  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3740 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded up to 220' and set first  
wooden plug at 220'. Placed 1/4  
sack hulls on top of plug. Displaced  
20 sacks cement through drill pipe on  
top of hulls. Mudded up to top of  
35' and set second wooden plug at  
and placed 1/4 sack hulls on top of  
plug. Filled hole to base of well  
cellar with 10 sacks cement.

Q-31-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address R. R. #2 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Karl E. Becker (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Karl E. Becker  
311 East Third, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of August, 19 54

My commission expires July 8, 1958

D. M. Kennedy Notary Public.

PLUGGING  
FILE SEC 13 T 21 R 14W  
BOOK PAGE 50 LINE 26

# WELL LOG

15.185-19478.0000

COMPANY **Petroleum, Inc. & Barrah & Garvin**

SEC. **13 T-21 R-14W**

FARM **McGINNY**

NO. **1**

LOC. **NW SW SE**


TOTAL DEPTH **3740**

COUNTY **Stafford County, Ks.**

COMM. **July 12, 1954.**

COMP. **July 21, 1954.**

CONTRACTOR **Garvey Drilling Company**



CASING **8-5/8" @ 226' w/175 cas.**

ELEVATION **1925 H.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

135	Sand
145	Shale
175	Sand
210	Clay
240	Shale & Shells
335	Sand
525	Shale & Shells
805	Red Red
835	Anhydrite
1605	Shale & Shells
2035	Line & Shale
2130	Line
2200	Line & Shale
2265	Shale
3160	Line & Shale
3235	Line
3335	Line & Shale
3620	Line
3668	Cherty Line
3740	Line
3740	E.T.D.

### Tons

Hebner:	3221 (-1296)
Brown Line:	3340 (-1415)
Lansing:	3352 (-1427)
Viola:	3597 (-1672)
Simpson:	3632 (-1707)
Arduoke:	3690 (-1765)

IVED  
BY COMMISSION

3-1-1954

NON DIVISION  
K. Kansas

### PLUGGING

FILE SEC 13 T-21 R-14W  
BOOK PAGE 50 LINE 26

State of KANSAS  
County of STAFFORD } SS:

I, O. C. Drake of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the McGINNY #1 well.

*O. C. Drake*

Subscribed and sworn to before me this 2nd day of August 19 54

My Commission Expires: 10-27-56

*Marjorie Bradshaw*  
NOTARY PUBLIC