

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Barton County, Sec. 4 Twp. 16 Rge. 11 (E) (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines C E / 2 NE SW

Lease Owner V. D. Sidey

Lease Name Charles Well No. 1

Office Address P. O. Box 387 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 9-20 19.57

Application for plugging filed 9-20 19.57

Application for plugging approved 9-20 19.57

Plugging commenced 9-20 19.57

Plugging completed 9-20 11:30 PM 19.57

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Brundridge Hoisington, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3362 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 300'. Set 1/2 sack of hulls and plug. Spotted 20 sacks of cement through drill pipe. Then filled hole to 25' with heavy mud. Set 1/2 sack of hulls and plug. Mixed and poured 5 sacks of cement in top of casing.

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 - 1957
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to V. D. Sidey Oil Company
Address P. O. Box 387
Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

V. D. Sidey (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. Box 387 Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of October, 1957.

Marguerite Byrne
Notary Public.

My commission expires September 17, 1960

PLUGGING
FILE SEC 4 T 16 R 11W
BOOK PAGE 48 LINE 3

SIDEY DRILLING CO.

BUILDING & LOAN BLDG. P. O. BOX 387

RUSSELL, KANSAS

Company **V. D. Sidey Oil Company**Sec. **4** T. **16** R. **11 W**
Loc. **C, E/2 NE SW**Farm. **Charles** No. **1**Total Depth **3362'**Comm. **9-9-57**Comp. **9-20-57**County **Barton**

Shot or Treated

Contractor **Sidey Drilling Company**

Issued

Casing		
20	10	305'
15½	8¼	
12½	6¾	
13%	5 5/16	

Elevation

Production **D & A**

Figures Indicate Bottom of Formations

0-100	Shale & shells	2889-2893	Heebner shale
100-303	Shale & shells	2893-2945	Lime & shale
303-340	Shale	2945-3001	Lime & shale
340-348	Grey sand	3001-3015	Lime KC
348-368	Shale	3015-3135	Lime
368-390	Grey sand	3135-3270	Lime
390-490	Shale & shells	3270-3333	Lime & shale
490-500	Shale	3333-3345	Shale
500-695	Red bed	3345-3362	Lime RTD
695-725	Anhydrite		
725-900	Shale		
900-1000	Shale & shells		
1000-1260	Shale & salt		
1260-1450	Shale & shells		
1450-1470	Lime		
1470-1520	Shale & shells		
1520-1610	Lime & shale		
1610-1770	Shale & limestone		
1770-1785	Lime		
1785-1900	Broken lime		
1900-2030	Lime		
2030-2155	Lime & shale		
2155-2195	Lime		
2195-2300	Shale & limeshells		
2300-2425	Shale & shells		
2425-2650	Shale & lime		
2650-2745	Lime		
2745-2889	Lime		


RECEIVED
STATE CORPORATION COMMISSION

OCT. 5 - 1957


CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

I, V. D. Sidey, of the Sidey Drilling Company, upon oath states that the above and foregoing is a true and correct copy of the Daily Drilling Report on the Charles #1 Well.


 V. D. Sidey

Subscribed and sworn to before me this 4th day of October, 1957


 Marguerite Byrne Notary Public

My Commission Expires: September 17, 1960

PLUGGING			
FILE	SEC	T. 16	R. 11 W
BOOK	PAGE	48	LINE 3