

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-009-06776-00-00
WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 16 Twp. 16S. Rge. 12 (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines... CSL SW 1/4
Lease Owner... Transwestern Oil Co.
Lease Name... Kultgen Well No. 1
Office Address... Milam Building, San Antonio, Texas
Character of Well (completed as Oil, Gas or Dry Hole)... Dry hole.
Date, well completed... April 17, 1941 19
Application for plugging filed... July 6, 1941 19
Application for plugging approved... July 12, 1941 19
Plugging Commenced... July 12, 1941 19
Plugging Completed... July 17, 1941 19
Reason for abandonment of well or producing formation... Dry hole.

If a producing well is abandoned, date of last production... 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?... yes

Name of Conservation Agent who supervised plugging of this well... C.T. Alexander
Producing formation... Quartzite Depth to top... Bottom... 3362' Total Depth of Well... 3362' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Quartzite	9'	3353'	3362'	8 5/8"	510'	None
				5 1/2"	3353'	2386'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

This well was plugged back from 3362' to 3030' with cement and Lane-Wells bridging plug. Then filled with mud from 3030' back to 2900', then set bridge with rock, burlap, and cement back to 2880'. Then ripped pipe and pulled 500' then filled with mud. Hole was then filled with heavy mud every 500', back to 510'. It was bridged with rock and cement back to 490', then filled with mud back to 20' of top of cellar. It was then bridged and cemented to within 8' of top of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to...
Address... Transwestern Oil Co.
Bushton, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.

J.V. Williams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.V. Williams

Bushton, Mo. (Address)

SUBSCRIBED AND SWORN to before me this 19 day of July, 19 41

My Commission Expires Feb. 1, 1943

My commission expires.....

Notary Public.




WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg, Wichita, Kansas.

TRANSWESTERN OIL CO.
L. Kuitgen No. 1.

SEC. 16 T. 16 R. 12W
CSL SE SW

Total Depth 3362
Comm. 2-17-41 Comp. 3-6-41
Shot or Treated.
Contractor. Iron Drilling Co.
Issued. 8-9-41

County Barton.



CASING.

85/8" 508' cemented.
5 1/2" 3353' cemented.

Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

surface	45
sticky clay and shale	125
shale & shells sticky shale	240
sand and shells	250
Dakota sand	405
Dakota series	510
shale and red rock	660
shale and shells	822
anhydrite	855
shale and shells	1310
shale shells & salt	1410
shale and shells	1538
lime and shale	1646
lime and shale sdy	1748
lime and shale	1910
broken lime	1950
sticky shale	1965
shale & sdy limo	1995
limo and shalo	2280
shale	2333
shale blue	2365
limo and shalo	2500
shale and limo shells	2614
shale and limo brkn	2680
limo Topoka	2707
lime and shalo	2805
limo	2829
limo	2930
broken limo	3013
limo and shalo	3153
K.C. limo	3216
limo	3343
sand	3349
Gorham sand	3362

Total Depth.

FILED IN 16 16 12W
BOOK PAGE 147 2