

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Barton County. Sec. 16 Twp. 16 Rge. (E) 12 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. SE-NE-NW
Lease Owner. Sunray Oil Corporation
Lease Name. Kultgen Well No. #1
Office Address. Box 195 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed. 6-9 1935
Application for plugging filed. 7-16 1945
Application for plugging approved. 7-19 1945
Plugging commenced. 7-20 1945
Plugging completed. 7-27 1945
Reason for abandonment of well or producing formation
Well Depleted.
If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr
Producing formation. Gorham? Depth to top. 3331 Bottom. 3341 Total Depth of Well. 3341 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Gorham Sand	Oil	3331	3341	15"	457'	193'
				7"	3325'	1258'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3341' to 3320' Cement 5 sacks.
3320' to 200' Mud
200' to 180' Cement 25 sacks.
180' to 15' Mud
15' to Cellar 15 sacks.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Sunray Oil Corporation
Address Box 195 8-17-45
Great Bend, Kansas

STATE OF _____, COUNTY OF _____
(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ed M. [Signature]
(Address) _____

SUBSCRIBED AND SWORN to before me this 14th day of August 1945
Marjorie Gunn
Notary Public.

My commission expires June 18, 1949

Sunray Oil Corporation

Well Log
of
Kultgen #1

Formation	Color	From	To	Remarks
Cellar			10	
Clay	yellow	10	40	
Shale	blue	40	245	
Water sand	light	245	255	2 b. w. per hr.
Shale	grey	255	270	
Shale	red	270	310	
Sandy lime	light	310	320	
Shale	light	320	355	
Red rock		355	360	
Shale	light	360	410	
Water sand		410	460	hole full water
Shale	dark	460	490	15 $\frac{1}{2}$ -475-on clamps
Shale	blue	490	495	
Sand	light	495	505	
Shale	blue	505	515	
Shale, broken		515	540	
Red mud		540	755	
Shale	blue	755	770	
Shale	red	770	805	
Anhydrite lime	light	805	830	13 3/8-805-4 an clamps
Shale	grey	830	835	
Red rock		835	1015	
Shale	blue	1015	1060	
Red rock		1060	1120	
Shale	blue	1120	1205	
Shale	grey	1205	1220	
Shale	Blue	1220	1245	
Salt	light	1245	1465	
Shale	blue	1465	1490	
Shale & red rock		1490	1505	
Shale	grey	1505	1515	
		1515	1625	
Lime	white	1625	1695	
Shale		1695	1700	
Lime, broken		1700	1725	
Shale	blue	1725	1730	
Lime	white	1730	1855	
Shale, broken		1855	1870	
Red rock		1870	1875	
Broken, lime		1875	1985	
Shells & red rock		1985	1995	
Shale	blue	1995	2000	
Shale	brown	2000	2015	
Lime, broken		2015	2035	
Shale & Shells	brown	2035	2060	
Lime		2060	2070	
Shale		2070	2085	
Lime, sandy		2085	2095	10" 2095-9 an clamps
Lime, broken		2095	2105	
Lime		2105	2115	
Shale		2115	2120	
Shells, hard		2120	2130	
Lime, broken		2130	2140	
Shale	blue	2140	2150	
Shells & red rock		2150	2175	
Shale, broken	grey	2175	2340	
Lime		2340	2350	

PLUGGING

FILE

16 160120

BOOK

20 17

STATE CORPORATION
COMMISSION

345

CORPORATION
1960

Shale		2350	2370	
Lime, broken		2370	2400	
Shale	blue	2400	2450	
Lime		2450	2470	
Shale		2470	2510	
Lime		2510	2520	
Shale & shells	blue	2520	2530	
Lime		2530	2538	
Shale		2538	2540	
Lime, broken		2540	2660	
Shale	grey	2660	2680	
Lime, broken		2680	2690	
Lime		2690	2715	
Lime, broken		2715	2750	
Lime	2750	2750	2835	
Shale		2835	2840	
Lime, broken		2840	2845	
Lime, hard		2845	2870	
Lime, broken		2870	2900	
Lime, hard		2900	2965	
Lime, broken		2965	2975	
Shale		2975	2980	
Broken lime		2980	2995	
Shale	brown	2995	3005	
Shale	blue	3005	3050	
Lime, hard		3050	3063	
Shale	red	3063	3065	
Lime, broken		3065	3070	
Lime, solid		2070	2085	
Shale, broken		3085	3100	
Lime broken		3100	3135	show oil-gas
Shale		3135	3140	3100 3105
Lime		3140	3255	
Shale	dark	3255	3265	
Lime		3265	3331	
oil sand		3331	3332	6 5/8 3325-8
oil sand		3332	3335	1400' oil in hole
shale grey		3335	3337	in 11 hrs.
Shale, chert, and sand		3337	3339	
Conglomerate and chert		3339	3341	hole filled 265' higher while taking first core 2 1/2 hrs.

(Signature)

Sunray Oil Corporation
Box 195
Great Bend, Kansas

Subscribed and sworn to before me this _____ day of _____ 1945

(Notary Public)

My commission expires _____

DRUGGING

FILE	16	16	212-01
BOOK	20	17	