

STATE OF KANSAS
STATE CORPORATION COMMISSION

**Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Biting Building,
Wichita, Kansas.**

SION 3-13-37

MAR 13 1937

Rice

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

**Strike out upper line
when reporting plug-
ging off formations.**

SESESE

NORTH

			0

Locate well correctly on above
640 A. Plat

Rice	County.	Sec.	Twp.	Rge.	(E).	7	(W).
Lease Name	Brothers						
Lease Owner	The Dickey Oil Company						
Office Address	Ellis-Singleton Building						
Character of Well (Oil, Gas or Dry)	Dry		Total Depth of Well	3569		Feet	
Date, well, completed	January 22		19		37		
Application for plugging and log of well filed	March 6		193		7		
Application for plugging approved	March 8		193		7		
Plugging Commenced	March 8		193		7		
Plugging Completed	March 12		193		7		
Reason for abandonment of well or producing formation	Dry						

If a producing well is abandoned, date of last production.....193.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....Yes.....

Name of Conservation Officer who supervised plugging of this well..... Alexander

Producing formation..... Depth to top..... Bottom.....

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

100 buckets of mud dumped in hole. 7" casing cut off at 2600'. Pulled out wood plug drove to bottom of 12 $\frac{1}{2}$ " surface pipe. Cemented with 10 sacks ash grove cement. Surface hole filled with mud, and top cemented with 10 sacks ash grove cement.



(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations?.....Yes

Was exception made?..... If so describe.

Correspondence regarding this well should be addressed to.....The Dickey Oil Company
Address.....Ellis Singleton Building, Wichita, Kansas

Address Ellis Singleton Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

R. J. Lewis

(employee of owner) or ~~owner or president~~

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature).

R. J. Lewis

.....
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of March, 1937

My commission expires Aug. 19, 1940

Leo Hasemeier

Notary Public.

15.159.19325.0000

THE DICKEY OIL COMPANY

Brothers Well No. 1

COMMENCED: 12-17-1936
 COMPLETED: 1-15-1937

LOCATION: NE/4 SE/4 NW/4 SW/4
 1-27-7 Rice Co., Ks.

Surface	107
shale	237
lime shells & shale	405
shale sheels	665
lime shells & shale	793
shale shells	913
salt	988
salt & shells	1062
lime	1909
shale	1100
lime	1116
lime broken	1244
lime	1270
broken lime & shale	1287
broken lime	1292
shale	1362
shale shells	1400
lime	1540
broken lime	1555
lime & shale	1657
shale shells	1712
SHALE	1762
shale & lime shells	1827
shale shells	1840
lime	1860
shale shells	1876
shale	1895
broken lime	1920
lime	1949
broken lime & shale	2015
shale	2045
lime	2079
shale	2160
lime	2170
shale	2216
shale & lime shells	2278
shale	2437
lime	2590
broken lime	2606
lime	2661
broken lime & shale	2687
lime	2712
broken lime	2735
lime	2760
broken lime	2791
shale	2850
lime	2861
shale & lime	2877
shale & lime shells	2920
shale	2985
lime	3055
shale	3083
lime, K. C.	3122
lime	3170
shale	2180
broken lime	3185
shale	3207
lime	3263
lime & shale	3307
broken lime	3323

Shale & Lime	3344
shale & lime shells	3378
shale & lime	3417
shale shells	3436
lime	3449
red rock	3452
conglomerate -	3470
red rock	3480
conglomerate	3488
chat	3492
water sand	3500
chat	3530
lime	3562
green shale	3569 TD

SHOWINGS

show oil	3481 - 3488
more oil	3489 - 3492 some water
HFW	3495

CASING RECORD

12 $\frac{1}{2}$ "	107'
7"	140 Joints

