

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 1 Twp. 21 Rge. 7 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NW NE NW

Lease Owner Thos. H. Allan

Lease Name Brothers Well No. #3A

Office Address 925 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed _____ 19__

Application for plugging filed 8-8-62 19__

Application for plugging approved _____ 19__

Plugging commenced 8-18-62 19__


Plugging completed 8-21-62 19__

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Cecil Jones

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3478 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 3/8"	188'	
				5 1/2"	3448'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3440' - mixed and ran 5 sacks cement
Bailed hole down to 200' - set rock bridge. Mixed and ran 20 sacks cement.
Mudded hole to 35' - set rock bridge - mixed and ran 10 sacks cement for top cap.

RECEIVED
STATE CORPORATION COMMISSION

AUG 24 1962

CONSERVATION DIVISION
Wichita, Kansas

8-24-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.

Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.

Box 364, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of August, 19 62

My commission expires 24 October 1964

Sidney D. Miller
Notary Public.



15.159.03987.0000

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **ALLAN & C R A**

SEC. 1 T. 21 S. 36

FARM **Brothers "A"** NO. 3

LOG. SW NE NW

TOTAL DEPTH **3479 1/2**

COMM. **11-26-50**


COMP. **12-14-50**

COUNTY **Rice**

SHOT OR TREATED

CONTRACTOR **Tom Allan**

ISSUED **1-6-51**



CASING

8 5/8" 188' com. w/150 SX

5 1/2" 3448' com. w/100 SX

ELEVATION **1691 RB**

Depth from Rotary bushings

PRODUCTION **Est. 60 Bbls. oil per day**

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil & sand	85	Tops:	
yellow sdy clay	115	Lansing	2982
redbeds	188	Cherty Conglomerate	3444
redbeds with anhy.		Mississippi	3470
strks	470		
gray shale with Anhy.			
strks	720		
salt & shale	1010		
shale & Anhy.	1315		
lime & shale	1410		
lime	1470		
cherty lime	1510		
lime & shale	1590		
lime	1680		
lime & shale	1740		
lime	1780		
lime & shale	1910		
shale & shells	2170		
lime	2220		
lime & shale	2280		
lime	2310		
lime & shale	2590		
lime w/shale strks	2870		
shale	2930		
lime & shale	2978		
sand	2982		
lime white	2992		
shale	2999		
lime with shale strks	3126		
shale	3137		
lime	3157		
shale	3181		
lime w/shale strks	3249		
red & gray shale	3265		
shale & shells	3325		
lime	3338		
shale & shells	3444		
vari colored chert & little medium sand	3448		
red mud	3451		
vari colored chert	3458		
red & gray shale	3466		
vari colored chert & white tripoli	3470		
white tripoli with dead oil stain	3479 1/2		
Total depth			