

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 9 Twp. 21S Rge. 13W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SE NW

Lease Owner Alpine Oil & Royalty Co., Inc.

Lease Name Fanshier Well No. 1

Office Address 800 Bitting Building, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed December 6, 1968 19

Application for plugging filed December 6, 1968 (by phone) 19

Application for plugging approved December 6, 1968 (by phone) 19

Plugging commenced December 6, 1968 19

Plugging completed December 6, 1968 19

Reason for abandonment of well or producing formation Nonproductive in commercial quantities

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. J. Warren

Producing formation Depth to top Bottom Total Depth of Well 3690 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8.5/8"	211'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from total depth to 600 feet. Plug and 50 sacks cement at 600 feet. Heavy mud to 200 feet. Second plug at 200 feet with 25 sacks cement. Top plug at 40 feet with 1/2 sack hulls. Plug to hold weight of Kelly. 15 sacks cement to bottom of cellar. 2 sacks cement for rat hole.

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place, Wichita, Kansas 67202


STATE OF Kansas, COUNTY OF Sedgwick, ss.

Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dwight J. Wilson
800 Bitting Bldg., Wichita, Kansas 67202
(Address)

My commission expires AND SWORN TO before me this 10 day of December, 1968

Evelyn Wanko Notary Public.



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1968
CONSERVATION DIVISION
Wichita, Kansas

J. H. FANSHIER #1
NW SE NW Section 9-21S-13W
Stafford County, Kansas

Commenced: November 26, 1968
Completed: December 6, 1968

OPERATOR - Alpine Oil Co., Inc.

DEPTH	FORMATION	REMARKS
From	To	
0	115	Surface soil and sand
115	135	Hard sand
135	209	Shale Ran 5 joints 8-5/8" casing, set @ 209' w/240 sacks cement.
209	770	Shale
770	810	Anhydrite
810	1580	Shale and shells
1580	3275	Lime and shale
3275	3690	Lime
3690	TD	Dry and abandoned.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NW SE NW Section 9-21S-13W, Stafford County, Kansas to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 10th day of December, 1968, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

