


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

STAFFORD STA. County. Sec. 9 Twp. 21s Rge. 13W (X) X(W)
Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner PETROLEUM, INC.
Lease Name FANSHIER "D" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed JULY 9 1961
Application for plugging filed JULY 11 1961
Application for plugging approved JULY 15 1961
Plugging commenced JULY 15 1961
Plugging completed JULY 22 1961
Reason for abandonment of well or producing formation NO PRODUCIBLE FORMATIONS.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. FRANK BROADFOOT
Producing formation ARBUCKLE Depth to top 3556 Bottom 3620 Total Depth of Well 3620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
ARBUCKLE	WATER & LITTLE OIL	3564'	3576'	8-5/8 5 1/2	256' 3618'	NONE 2274'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

(PLUGGED BACK T.D. 3609')

FILLED HOLE FROM 3609' TO 3550' WITH CRUSHED ROCK. PLACED 5 SACKS CEMENT ON TOP OF CRUSHED ROCK. MUDDED UP WITH HEAVY MUD TO 250'. MADE SOLID ROCK BRIDGE AT 250'. PLACED 20 SACKS CEMENT ONTO ROCK BRIDGE. MUDDED UP WITH HEAVY MUD TO 40'. MADE SOLID ROCK BRIDGE AT 40'. PLACED 10 SACKS CEMENT ONTO ROCK BRIDGE TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1961

CONSERVATION DIVISION
Wichita, Kansas

8-2-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MORGAN WELL PLUGGING SERVICE
Address 102 WEST 18TH STREET, HUTCHINSON, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or ~~XXXXXXXXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 31ST day of JULY, 1961

Arthur J. Miles
Notary Public.

My commission expires APRIL 14, 1963



WELL LOG

15.185.19491.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 9 T. 21S R. 13W

FARM FANSHIER "D" NO. 1

LOC. SE, SE, NE


TOTAL DEPTH 3620'

COUNTY STAFFORD CO., KANSAS

COMM. June 15, 1961

COMP. June 26, 1961

CONTRACTOR GARVEY DRILLING COMPANY



casing 8-5/8" @ 256' w/200 sax.
5 1/2" @ 3619' w/75 sax.

ELEVATION 1884' DF

PRODUCTION Dry and Abandoned

FIGURES INDICATE BOTTOM OF FORMATIONS

190	Surface sand, clay & gravel
256	Shale & red bed
745	Red bed & shale
770	Anhydrite
1075	Shale & shells
1590	Shale
2135	Lime
2915	Shale & lime
3030	Lime & shale
3172	Lime
3300	Lime & shale
3620	Lime
3620	T. D.

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1961

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } SS

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 FANSHIER "D" well.

Verne A. Morris

Subscribed and sworn to before me this 6th day of July 19 61

My Commission Expires: April 14, 1963

Arthur J. Miles
NOTARY PUBLIC