

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 9 TWP. 21s RGE. 13w E/W
Location as in quarters or footage from lines:
NE SW SE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Southern States Oil Co.
Lease Name Harvey Fanshier #1 Well No. _____
Office Address P.O. Box 1365, Great Bend, Ks. 67530.
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11/10/82
Plugging completed 11/12/82
Reason for abandonment of well or producing formation _____
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom T.D. 3620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	287'	none
				5 1/2"	3619'	178'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Found cement at 210' between 5 1/2" & 8-5/8. Shot pipe at 182', pulled
6 joints. Plugged well with 25 sacks cement, 1 hull, 8 gel, 25 cement,
2 gel, 1 hull, 100 cement. Well is on Vac. Pulled head & checked hole,
found top of cement @ 174', filled to base of cellar with 2 1/2 yards
Ready Mix.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 1982



My Commission expires: _____

Irene Hoover
Notary Public.
STATE CORPORATION COMMISSION
NOV 18 1982
CONSERVATION DIVISION
Wichita, Kansas

ROTARY DRILLING LOG

Icer Addis #1 Harvey Fanshier
NE SW SE/4 9-21S-13W
Stafford County, Kansas

Contractor: Omega Drilling, Inc.

Commenced: January 22, 1968

Completed: February 1, 1968

RECEIVED
STATE CORPORATION COMMISSION

OCT 04 1982

CONSERVATION DIVISION
Wichita, Kansas

Casing Record:

Cemented 8 5/8" surface casing
at 287' with 250 sacks.

Cemented 5 1/2" casing at 3619'
with 125 sacks.

FORMATIONS

290	Sand and shale
465	Shale
770	Shale and Red Bed
790	Anhydrite
1046	Shale
1604	Shale and shells
2070	Lime and shale
2073	Shale
3050	Lime and shale
3590	Lime
3595	Lime and chert
3620	Lime
3620	Rotary Total Depth

We certify that the above log is true and correct to the best of our knowledge and belief.

OMEGA DRILLING, INC.)

By F. S. Woodside, Jr., President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas, County of Sedgwick, this 6th day of February, 1968.

Mary W. Lawrence
Mary W. Lawrence, Notary Public

My commission expires February 28, 1971.