

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Also Attach to this Report
Maps Required Where
Map or Diagram Shows
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

Locate well correctly on above
Section Plat

Stafford County, Sec. 9 Twp. 21 S. Rgc. 13 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SW NE SE

Lease Owner Icer Addis

Lease Name FANSHIER Well No. 5

Office Address P. O. Drawer 8038 - Wichita, Ks. 67208

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 16 19 74

Application for plugging filed May 16 19 74

Application for plugging approved May 16 19 74

Plugging commenced May 16 19 74

Plugging completed May 16 19 74

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein

Producing formation Depth to top Bottom Total Depth of Well 3638 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole full of heavy mud
Set plug at 500' with 40 sacks cement thru drill pipe.
Middle plug set at 300' with 25 sacks cement thru drill pipe.
Top plug set at 40' with 1/2 sk. hulls and 15 sacks cement
2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Duke Drilling Co.
Address Box 823 - Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton ss.

Leonard Williamson (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

Box 823 - Great Bend, Ks. 67530

Subscribed and Sworn to before me this 20 day of May 19 74

Marathy M. Hague
Notary Public.

DRILLERS' WELL LOG

DATE COMMENCED: May 9, 1974
 DATE COMPLETED: May 15, 1974

Icar Acid
 PANSHER #5
 SW NE SE
 Section 9-2215-RL3r
 Stafford County, Kansas

ELEVATION: 1870 R.B.

0 - 24' Sand
 24 - 124' Hard Sand
 124 - 305' Shale & Sand Streaks
 305 - 754' Red Bed
 754 - 777' Anhydrite
 777 - 1565' Shale & Shells
 1565 - 3183' Lime & Shale
 3183 - 3188' Shale
 3188 - 3203' Lime & Shale
 3203 - 3219' Lime
 3219 - 3307' Shale
 3307 - 3320' Lime & Shale
 3320 - 3541' Lime
 3541 - 3638' Shale, Lime Chert
 3638' RTD

FORMATION DATA

ANHYDRITE	754
HELVETIC	3183
TORONTO	3203
DOUGLAS	3219
BROWN LIME	3307
KANSAS CITY	3320
BASE K.C.	3541
CONGLOMERATE	3551
VIOLA	3557
SIMPSON	3616
RTD	3638

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 21 1974
 CONSERVATION DIVISION
 Wichita, Kansas

SURFACE PIPE: Set used 2-5/8", 237
 pipe at 305' with 235 sacks of 60/40
 portlx, 2 1/2 Gal, 3 cc.

AFFIDAVIT

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Leonard Williamson of lawful age does swear and state that the facts and
 statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 20 day of May 1974.

My Comm. Expires:
April 11, 1978

Maecy M. Hague
 Notary Public