


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 9 Twp. 21S Rge. 13W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SW SW SE  
Lease Owner The Texas Company  
Lease Name C. M. Fanshier Well No. 1  
Office Address 614 Bitting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry  
Date well completed April 13 19 57  
Application for plugging filed May 27 19 57  
Application for plugging approved May 28 19 57  
Plugging commenced June 2 19 57  
Plugging completed June 2 19 57  
Reason for abandonment of well or producing formation



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundege  
Producing formation Depth to top Bottom Total Depth of Well 3730 Feet  
Show depth and thickness of all water, oil and gas formations. PBD 3497

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	782	None
				7"	3688	3168

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3497' to 3440' - Sand  
3440' to 3415' - 5 Sacks Cement  
3415' to 260' - Heavy Mud  
260' to 240' - Rock Bridge  
240' to 200' - 25 Sacks Cement  
200' to 25' - Heavy Mud  
25' to 20' - Rock Bridge  
20' to Bottom of Cellar - 10 Sacks Cement

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & S Pipe Pulling Company  
Address Box 192, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
M. C. Harrell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. C. Harrell  
614 Bitting Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 5th day of June, 19 57

My commission expires September 20, 1960  
Notary Public.

PLUGGING  
FILE SEC T  
BOOK PAGE LINE

JUN 6 X 1957  
CONSERVATION DIVISION  
Wichita, Kansas

15.185.1291.0000

THE TEXAS COMPANY

Tulsa, Oklahoma

DRILLERS WELL LOG

C. W. Fanshier #1

SW SW SE Sec. 9-21 S-13W  
Stafford County, Kansas

Commenced Rotary Drilling: 3-16-57

Elevation:

Completed Rotary Drilling: 3-31-57

Initial Production:

Total Depth 3685

Contractor: Powell Drilling Company

Casing Record: 769' (24 jts.) 10-3/4" 24# Surface Casing  
3685' (111 jts) 7" 20# Rd. Thd. Casing

<u>Strata</u>	<u>Depth</u>
Clay and Sand	90
Hard Sand	130
Shale	210
Shale and Sand	270
Shale and Shells	465
Red Rock, Sand & Shells	615
Red Rock	759
Anhydrite	769
Cement	769
Anhydrite	782
Shale and Shells	1550
Shale	1610
Ft. Riley Lime	1765
Lime	1895
Shale and Lime	2060
Shale, Lime & Shells	2385
Shale & Lime	2537
Shale & Shells	2810
Shale & Lime	3015
Lime	3216
Shale	3322
Lime	3592
Cherty Lime	3665
Lime	3685 T.D.

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

POWELL DRILLING COMPANY

By [Signature]

Signed and sworn to in my presence this 2nd day of April, 1957 by C. M. Powell, Jr., partner in the Powell Drilling Company.

[Signature]  
Notary Public

My commission expires Oct. 13, 1960.

PLUGGING			
FILE	SEC 9	T. 21	13W
BOOK	PAGE 15	LIN. 37	

RECEIVED  
STATE CORPORATION COMMISSION

JUN 6 1957

CONSERVATION DIVISION  
Wichita, Kansas

15.185-12191.0000

# LOG OF WELL

FORM PO-214 SHEET 1 (4-54) 35M

## C. M. FANSHIER WELL NO. 1

SHEET 1

OWNER The Texas Company DIVISION Oklahoma DATE MADE April 22, 1957  
 DISTRICT Kansas LEASE C. M. Fanshier WELL NO. 1  
 STATE Kansas COUNTY OR PARISH Stafford TWP. 21S RANGE 13W SEC. 9  
 LOCATION OF WELL SW SW SE

COMMENCED RIGGING UP 3-16-57 COMMENCED DRILLING 3-16-57 COMPLETED DRILLING 4-13-57  
 DAY DRILLER \_\_\_\_\_ NIGHT DRILLER \_\_\_\_\_ CONTRACTOR Powell Drilling Co.  
 CABLE FROM 3685' TO 3730' ROTARY FROM 0 TO 3685' COMPANY RIG NO. GL-1889  
 TOTAL DEPTH 3730 MEASURED BY M. C. Harrell ELEVATION DF-1891  
PBTD 3497 KB-1893

### CASING RECORD

SIZE	WEIGHT	PUT IN WELL		PULLED OUT		LOST IN WELL		SHOES		PACKERS		
		FEET	INS.	FEET	INS.	FEET	INS.	LENGTH	MAKE	KIND	LENGTH	SET AT
10-3/4"	32.75#	782				(H-40 R-2		New casing)				FT.
7"	20 #	3688				(R-2 J-55		New Casing)				FT.
												FT.
												FT.
												FT.
												FT.
10-3/4" casing set at 768' with 450 sacks Pozmix, 4% Gel, 3 sacks CC, cement												FT.
7" casing set at 3684' with 75 sacks cement, 3% Gel.												FT.

WAS CASING CEMENTED? \_\_\_\_\_ IF SO, HOW MANY SACKS OF CEMENT USED? \_\_\_\_\_  
 LINER: STATE SIZE AND WEIGHT \_\_\_\_\_ WHERE SET \_\_\_\_\_ FT. AND INS. PERFORATED \_\_\_\_\_  
 HOW PUT TOGETHER \_\_\_\_\_ COUPLING \_\_\_\_\_ FLUSH-JOINT \_\_\_\_\_ INSERTED \_\_\_\_\_  
 REMARKS: \_\_\_\_\_

### EQUIPMENT RECORD

TUBING				SUCKER RODS				PUMPING OUTFIT			
SIZE	WEIGHT	FEET	INS.	FEET	INS.	SIZE AND KIND	DESCRIPTION	KIND	SIZE, ETC.		

Completed testing 4-14-57

FLOWING, PUMPING, GASSER OR DRY. Dry PRODUCTION FIRST 24 HOURS \_\_\_\_\_ PRODUCTION SETTLED \_\_\_\_\_  
 IF GAS WELL, OPEN FLOW CAPACITY \_\_\_\_\_ SHUT IN PRESSURE \_\_\_\_\_ ROCK PRESSURE \_\_\_\_\_  
 KIND OF SHOT \_\_\_\_\_ SIZE OF SHOT, QUARTS \_\_\_\_\_  
 NUMBER OF SHELLS \_\_\_\_\_ SIZE OF SHELLS \_\_\_\_\_ INCHES, DIAMETER \_\_\_\_\_  
 LENGTH OF SHELLS \_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ TOP OF SHOT \_\_\_\_\_  
 BOTTOM OF SHOT \_\_\_\_\_ ANCHOR \_\_\_\_\_ WELL BRIDGED TO \_\_\_\_\_  
 TOTAL DEPTH OF WELL \_\_\_\_\_ NUMBER OF SHOT \_\_\_\_\_ PRODUCTION BEFORE SHOT \_\_\_\_\_ BBLs. PER DAY \_\_\_\_\_  
 PRODUCTION AFTER SHOT \_\_\_\_\_ BBLs. PER DAY, SHOT FURNISHED BY \_\_\_\_\_  
 NAME OF SHOOTER \_\_\_\_\_ SHOT INSPECTED \_\_\_\_\_ BY \_\_\_\_\_ (COMPANY EMPLOYEE)  
 COMMENCED DRILLING DEEPER \_\_\_\_\_ COMPLETED \_\_\_\_\_ DRILLING DEEPER \_\_\_\_\_  
 TOTAL DEPTH \_\_\_\_\_ PRODUCTION FIRST 24 HOURS \_\_\_\_\_ PRODUCTION SETTLED \_\_\_\_\_

REMARKS: C. M. Fanshier #1  
Hazel West Pool  
TD 3730-PBTD 3497  
Completed Drilling 4-13-57  
Completed Testing 4-14-57

NOTE: IF WELL WAS DRY, STATE UNDER REMARKS, WHEN, HOW, AND BY WHOM PLUGGED.  
 STATE UNDER REMARKS ANYTHING OF INTEREST NOT COVERED IN LOG.  
 IF THE SPACE PROVIDED FOR REMARKS IS NOT SUFFICIENT WRITE ON BOTTOM OF LAST SHEET OF LOG.

TOTAL NUMBER OF SHEETS 2

13.25, \$550.00, \$500.00, \$350.00 (wait)