


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Rice County, Sec. 27 Twp. 21 Rge. 7E (E) (W)  
Location as "NE/CNW/SW" or footage from lines  
Sterling Drilling Company  
Lease Owner  
Lease Name Engelland #E #1 Well No.  
Office Address  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 6/16/72 19  
Plugging completed 6/20/72 19  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justice  
Producing formation Depth to top Bottom Total Depth of Well 3442 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRGM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8	176	none
				5 1/2"	3427	2942'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3442', ran sand to 3390' and ran 5 sacks of cement.  
Loaded hole with water, shot pipe at 2989', 2924', pulled 92 joints.  
Set rock bridge 210 to 200' and ran 3 5 sacks of cement. Mudded to 40',  
rock bridge to 30' and ran 10 sacks of cement. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS


STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 21st day of June, 1972

Margaret Melcher  
Notary Public.

My commission expires



STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

WELL LOG ----- ENGELLAND "E" #1  
Located: C NE NW, Sec. 27-21S-7W, Rice County, Kansas

OWNER: Sterling Drilling Company and Martin Oil and Gas Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 11, 1972  
COMPLETED: March 16, 1972

TOTAL DEPTH: 3428'

<u>LOG</u>		<u>CASING RECORD</u>
0 - 56	Sand	Ran 4 joints 8 5/8" 20# new seamless casing, 164.61' of pipe set at 176' K.B. with 160 sacks Pozmix #1 (60/40) with 3% HA-5. Plug down 8:55 PM, 3-11-72.
56 - 178	Shale and Red Bed	
178 - 335	Shale	
335 - 1109	Shale, Salt and Lime	
1109 - 3210	Lime and Shale	
3210 - 3390	Lime	Ran 108 joints 5 1/2" 14# 8rd tested 4000#, 3430.55' threads off set at 3427' with 75 cu. ft. salt saturated cement. Plug down 7:20 AM, 3-16-72.
3390 - 3428	Lime and Chert	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1972  
CONSERVATION DIVISION  
Wichita, Kansas