


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rice County. Sec. 27 Twp. 21 Rge. 7 (E) W (W)  
Location as "NE/CNW&SW" or footage from lines C/NE/NW  
Lease Owner Dutton's Inc  
Lease Name Engelland Well No. 1  
Office Address 2400 North Main, Hutchinson, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed March 19, 1967 19  
Application for plugging filed March 23, 1967 19  
Application for plugging approved March 19, 1967 19  
Plugging commenced March 19, 1967 19  
Plugging completed March 19, 1967 19  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman  
Producing formation Depth to top Bottom Total Depth of Well 3444 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud to 220 feet  
Set plug with 1/3 sack hulls 25 sacks of cement  
Filled hole with rotary mud to 40 feet  
Set plug with 1/3 sack hulls dumped 2 sacks of cement  
Dumped 3 sacks of cement in cellar

RECEIVED  
STATE CORPORATION COMMISSION

MAR 27 1967

CONSOLIDATED DIVISION  
WICHITA, KANSAS

3-27-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triple 'D' Drilling Company, Inc  
Address 2400 North Main, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
Robert J. Dutton (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert J. Dutton  
2400 North Main, Hutchinson, Kansas  
(Address)

Subscribed and Sworn to before me this 23rd day of March, 1967

My commission expires March 4, 1969

M. L. Bowman  
Notary Public

ENGELLAND #1  
Center/NE¼/NW¼ 27-21-7W  
Rice County, Kansas  
Operator - Dutton's Inc  
Drilling Contractor - Triple 'D' Drilling Co., Inc  
Date Spudded - March 8, 1967  
Date Completed - March 19, 1967

0 to 233 Sand & Shale  
233 to 1,080 Shale & Shells  
1,080 to 2,705 Lime and shale  
2,705 to 2,750 Lime  
2,750 to 2,812 Sandy Lime  
2,812 to 2,823 Lime  
2,823 to 2,915 Lime and Sand  
2,915 to 3,345 Lime  
3,345 to 3,423 Lime and Shale  
3,423 to 3,428 Chert  
3,428 to 3,444 Chert and Lime TD

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 27 1967  
CONSERVATION DIVISION  
WICHITA, KANSAS


CASING RECORD

Set 233 ft of ~~12 1/8~~ 8-5/8" - 200 sacks of cement

STATE OF KANSAS )  
                          )SS:  
COUNTY OF RENO )

I, Robert J. Dutton, President of Dutton's Inc., do  
solemnly swear that the above is a true copy of drilling log on well  
above mentioned.

Subscribed and sworn to this 22nd day of March,  
1967.

  
Robert J. Dutton

My Commission expires:  
March 4, 1969

  
M. L. Bowman, Notary Public