


Give All Information Completely
Make Required Affidavit -
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

PAWNEE County. Sec. 2 Twp. 23 Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner HILTON DRILLING COMPANY, INC.
Lease Name HINES Well No. 2
Office Address 925 PATTON ROAD, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed NOVEMBER 5 19 55
Application for plugging filed JUNE 23 19 59
Application for plugging approved JUNE 26 19 59
Plugging commenced JULY 3 19 59
Plugging completed JULY 8 19 59
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production SEPTEMBER 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT - ST. JOHN, KANSAS
Producing formation CONGLOMERATE Depth to top 4152 Bottom 4238 Total Depth of Well 4267 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215	NONE
				5-1/2"	4265	3527

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUG BACK WITH SAND TO 4145' DUMP 5 SACKS CEMENT.
PULL 5-1/2" CASING, (3527'), PLUG SURFACE WITH PUMP
TRUCK (GLOBE CEM. CO.) MIX AND PUMP IN 30 SACKS
GEL MUD, PUT IN PLUG, MIX AND PUMP IN 100 SACKS
CEMENT SHUT IN WITH 75# PRESSURE

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1959

CONSERVATION DIVISION
Wichita, Kansas

7-23-59

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ACE PIPE PULLING COMPANY
Address Box 304, GREAT BEND, KANSAS

EM HILTON
STATE OF KANSAS, COUNTY OF BARTON, ss.
HENRY PEABOCK - LAND DEPARTMENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *EM Hilton*
GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13TH day of JULY 19 59

Carmen Reinhardt Leiker
CARMEN REINHARDT LEIKER Notary Public.

My commission expires JANUARY 26, 1963

PLUGGING
FILE SEC. 2 T. 23 R. 17W
BOOK PAGE 47 LINE 4

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 500 East Murdock, Wichita, Kansas

15-145-01128-0000


COPY

Company - HILTON DRILLING CO.
 Form - Hinos No. 2

SEC. 2 T. 23 R. 17N
 NE NE SW

Total Depth 4267'
 Comm. 10-11-55 Comp. 10-25-55
 Shot or treated.
 Contract No.
 Issued. 8-4 -56

County Pawnee
 KANSAS



3" 215' com w/200 sx
 5 1/2" 4265' com w/150 sx

200' RB

86 EOPD

Figure 1 - Hole Bottom of Form No. 2

clay, sand	110
sand, gravel	100
red rock	165
shale	390
red rock, shale	570
sand	630
red rock	1100
anhydrite	1130
shale, shells	1912
shale, lime	2145
lime	2325
sand, lime	2405
lime	2515
shale, lime	3080
lime	3645
shale, lime	3712
lime	4130
lime, shale, chert	4165
lime, chert	4168
shale, chert, sand	4208
lime, chert, shale	4236
shale, chert	4267
Total Depth	

Tops: Scout	
Heebner	3612
Brown Lime	3719
Lansing	3729
Conglomerate shale	4135
Conglomerate chert	4152
Viola	4238