


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

15-45-01129-0000



Locate well correctly on above Section Plat

PAWNEE County. Sec. 2 Twp. 23 Rge. 17 (E) (W)  
Location as "NE/CNW/SW" or footage from lines C-WL-SW  
Lease Owner HILTON DRILLING COMPANY, INC.  
Lease Name HINES Well No. 3  
Office Address 925 PATTON ROAD, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL  
Date well completed MARCH 19 56  
Application for plugging filed JUNE 23 19 59  
Application for plugging approved JUNE 26 19 59  
Plugging commenced JUNE 27 19 59  
Plugging completed JULY 1 19 59  
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production JULY 19 58  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT - ST. JOHN, KS.  
Producing formation CH. CONGL. Depth to top Bottom Total Depth of Well 4268 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215'	NONE
				5-1/2"	4266'	3239'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUG BACK WITH SAND TO 4190' DUMPED 5 SX CEM. PULL 5 1/2"  
CASING, PLUG SURFACE WITH PUMP TRUCK (GLOBE) MIX AND PUMP  
IN 30SX GEL MUD PUT IN PLUG MIX AND PUMP IN 100 SX CEM  
SHUT IN WITH 75 LBS PRESSURE.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 24 1959

CONSERVATION DIVISION  
Wichita, Kansas

7-24-59

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor ACE PIPE PULLING COMPANY  
Address GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
E. M. HILTON - PRESIDENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *E. M. Hilton*  
GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 22ND day of JULY 19 59

*Carmen Reinhardt Leiker*  
CARMEN REINHARDT LEIKER Notary Public.

My commission expires JANUARY 26, 1959

PLUGGING  
FILE SEC 2 T. 23 R. 17W  
BOOK PAGE 47 LINE 3

WELL LOG BUREAU - AMERICAN GEOLOGICAL SOCIETY  
 503 East Woodward, Wichita, Kansas

COPY

Company- HILTON DRILG.  
 Firm- Hines

No. 3

SEC. 2 T. 23 R. 17W  
 CWL SW

15-145-01128-0000

Total Depth. 4268

Com. No. 2-27-56

Comp. 3-12-56


Shot or Treated.

Contr. No.

Issued. 8-4-56

County Pawnee

KANSAS



CASING:

8 5/8" 215' w/200 sx cem  
 5 1/2" 4266' w/150 sx cem.

Elevation 2087 DF

Production 42 BOPD

Figures indicate Bottom of Formation

sand -clay-shale	215
clay	400
red rock	580
sand	660
red rock-shale shells	955
red rock-sand-shale	1105
Anhydrite	1130
shale shells	1910
shale lime	2247
lime	2615
shale lime	2955
shale	3040
shale lime	3330
lime	3490
shale-lime	3590
lime	3653
shale-lime	3743
lime	4227
chert-shale-lime	4268
Total Depth	

TOPS: Scout	
Heebner	3633
Kansas City	3750
Conglomerate	4180