


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

PAWNEE County. Sec. 2 Twp. 23 Rge. 17 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner HILTON DRILLING COMPANY, INC.
Lease Name HINES Well No. 1
Office Address 925 PATTON ROAD, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed AUGUST 8 19 55
Application for plugging filed JUNE 23 19 59
Application for plugging approved JUNE 26 19 59
Plugging commenced JULY 9 19 59
Plugging completed JULY 12 19 59
Reason for abandonment of well or producing formation DRY



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production AUGUST 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT - ST. JOHN, KANSAS
Producing formation CONGLOMERATE Depth to top Bottom Total Depth of Well 4290 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	226	NONE
				5-1/2"	4288	3390

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

PLUG BACK WITH SAND TO 4190' DUMP 5 SACKS CEMENT, REMOVE
PULL 5-1/2" CASING (3390'), PLUG SURFACE WITH PUMP TRUCK
(GLOBE CEM. CO.) MIX AND PUMP IN 30 SACKS GEL MUD PUT IN
PLUG, MIX AND PUMP IN 100 SACKS CEMENT QUICK SET, SHUT IN
PRESSURE 75#.

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ACE PIPE PULLING COMPANY
Address BOX 304, GREAT BEND, KANSAS

EM HILTON
STATE OF KANSAS, COUNTY OF BARTON, ss.
HENRY PEACOCK - LAND DEPARTMENT
(employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *EM Hilton*
GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of JULY 19 59

My commission expires JANUARY 26, 1963
Carmen Reinhardt Leiker
CARMEN REINHARDT LEIKER Notary Public.

PLUGGING
FILE SEC 2 T 23 R 124
BOOK PAGE 47 LINE 5

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


15-145-61127-0000

Company- HILTON DRILLING CO.
Farm- Hines No. 1

SEC. 2 T. 23 R. 17W
NW NW SW

Total Depth. 4290'
Compl. 7-26-55 Comp. 8-8-55
Shot or Treated.
Contracted.
Issued. 7-28-56

County Pawnee
KANSAS



CASING:

8 5/8" 226' com w/200 sx
5 1/2" 4288' com w/150 sx

Elevation. 2082'

Production. 1332 BOPD

Figures in locate E form of Form 101a

sand	85
sand, shale	210
shale	226
shale, shells	385
red rock, sand	655
red rock	1120
anhydrite	1145
shale, shells	1420
shale, shells, salt	1720
shale, lime	2050
lime	2610
shale, lime	3325
lime	3645
shale, lime	3758
lime	4214
lime, shale, chert	4239
lime, chert	4255
shale, lime chert	4290
Total Depth	

Tops: Scout	
Hoebner	3645
Lansing	3765
Conglomerate	4186
Conglomerate Ch.	4200

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION
Wichita, Kansas