

15-145-01126-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County. Sec. 2 Twp. 23 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW  
Lease Owner Colorado Oil Company  
Lease Name Boyd Well No. 6  
Office Address 915 Union National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed December 23 19 55  
Application for plugging filed January 24 19 69  
Application for plugging approved January 27 19 69  
Plugging commenced February 13 19 69  
Plugging completed February 25 19 69  
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 19 63  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Conglomerate Depth to top 4166 Bottom Total Depth of Well 4260 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None
				5-1/2"	4259'	3201'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran sand from 4224' to 4150'. Mixed & dumped 5 sacks cement.  
Loaded hole, shot pipe @ 3184'. Worked pipe loose & pulled 101 joints. Pumped 20 sacks mud, 5 sacks bulls and 100 sacks cement.

PLUGGING COMPLETE

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas

3-2-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.  
Address P. O. Box 405, Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs  
915 Union National Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 19 69

My commission expires February 19, 1973

Betty J. McElwain  
Notary Public.

DRILLERS LOG

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1956  
CONSERVATION DIVISION  
Wichita, Kansas

Boyd No. 6  
Loc: NE NE NW  
Sec: 2-23S-17W  
Pawnee County, Kansas  
Company: Colorado Oil & Gas Corporation  
Contractor: Honaker Drlg., Inc.

Comm: 12- 6-55  
Comp: 12-17-55  
Rotary Total Depth: 4260  
Casing: 8 5/8" 249'  
5 1/2" 4259'

15-145-01126-0000

0	40	Top Soil & Sand	
40	90	Sand & Gravel	
90	200	Sandy Clay	
200	250	Blue Shale	8 5/8" casing cemented at
250	550	Shale & Red Bed	249' with 175 sacks cement
550	645	Sand	& 2% calcium chloride
645	820	Sandy Red Bed	
820	1110	Red Bed & Shale	
1110	1135	Anhydrite	
1135	1850	Shale & Shells	
1850	2060	Shale & Lime	
2060	2225	Lime & Shale	5 1/2" casing cemented at
2225	2425	Lime	4259' with 175 sacks cement
2425	4151	Lime & Shale	
4151	4260	Chert & Shale	
4260		Total Rotary Depth	

I certify that this is the true and correct copy of the above log to the best of my knowledge.

  
H. S. Forbes

Subscribed and sworn to before me this 12th day of January, 1956.

  
Kenneth G. Fischer, Notary Public

My Commission Expires: 6-25-59