


15-145-01125-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Pawnee County. Sec. 2 Twp. 23 Rge. (E) 17 (W)  
Location as "NE/CNW/SW" or footage from lines C NW/4  
Lease Owner Colorado Oil Company  
Lease Name Boyd Well No. 5  
Office Address 915 Union National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) ~~Oil~~ Oil  
Date well completed November 28 1955  
Application for plugging filed January 24 1969  
Application for plugging approved January 27 1969  
Plugging commenced February 19 1969  
Plugging completed February 25 1969  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production January 1967  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Conglomerate Depth to top 4171 Bottom \_\_\_\_\_ Total Depth of Well 4278 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	255'	None
				5-1/2"	4277'	3220'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole, ran sand, mixed & dumped 5 sacks cement. Loaded hole, shot pipe @ 3295', shot pipe @ 3202'. Worked pipe loose and pulled 102 joints. Pumped 20 sacks mud, 5 sacks hulls and 100 sacks cement.

PLUGGING COMPLETE

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 6 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
3-6-69

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co., Inc.  
Address P. O. Box 405, Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs  
915 Union National Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of March, 1969

My commission expires February 19, 1973

Betty J. McElwain  
Betty J. McElwain Notary Public.

15-145-01125-0000

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

Boyd No. 5  
Loc: C NW/4  
Sec: 2-23S-17W  
Pawnee County, Kansas  
Company: Colorado Oil & Gas Corp. &  
Honaker Drig., Inc.  
Contractor: Honaker Drig., Inc.


Comm: 11-10-55  
Comp: 11-24-55  
Rotary Total Depth: 4278  
Casing: 8 5/8" 254'  
5 1/2" 4278'

0	75	Surface Sand & Clay	
75	395	Shale & Shells	
395	580	Red Bed	
580	670	Sand	8 5/8" casing cemented at
670	1075	Shale & Shells	254' with 175 sacks cement
1075	1110	Anhydrite	& 2 sacks calcium chloride
1110	1960	Shale & Shells	
1960	1975	Lime	
1975	2125	Lime & Shale	
2125	2245	Lime & Shale Streaks	
2245	2360	Lime	
2360	2450	Lime & Shale	5 1/2" casing cemented at
2450	2510	Lime	4278' with 175 sacks cement.
2510	3420	Shale & Lime	
3420	3627	Lime & Shale	
3627	3631	Shale	
3631	3680	Lime	
3680	3735	Lime & Shale	
3735	3755	Lime	
3755	3791	Lime & Shale	
3791	4135	Lime	
4135	4170	Lime & Shale	
4170	4240	Cherty Conglomerate	
4240	4278	Lime & Chert	
4278		Total Rotary Depth	

I certify that this is the true and correct copy of the above log to the best of my knowledge.

  
H. S. Forbes

Subscribed and sworn to before me this 29th day of November, 1955.

  
Kenneth G. Fischer, Notary Public

My Commission Expires: 6-25-59