


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD **15-145-01124-0000**



Locate well correctly on above Section Plat

Pawnee County, Sec. 2 Twp. 23 Rge. (E) 17 (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NE  
Lease Owner Colorado Oil Company  
Lease Name Boyd Well No. 4  
Office Address 915 Union Natl. Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed October 16 19 55  
Application for plugging filed January 24 19 69  
Application for plugging approved January 27 19 69  
Plugging commenced March 11 19 69  
Plugging completed March 20 19 69  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production December 19 65  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Congl. Chert Depth to top 4160 Bottom \_\_\_\_\_ Total Depth of Well 4265 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	None
				5-1/2"	4264'	3026'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran sand to 4150', mixed & dumped 5 sacks cement. Rigged up over 5-1/2", had hole loaded. Shot pipe @ 3012', worked pipe loose & pulled 90 joints, pulled 9 more joints. Pumped 20 sacks mud, 5 sacks hulls & 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 1 1969 4-1-69  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Knight Casing Pulling Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs  
915 Union Natl. Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of March, 1969

My commission expires February 19, 1973

Betty J. McElwain  
Betty J. McElwain Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

15-145-61124-0000

Wells # 4  
Loc: NW NW NE  
Sec: 2-23S-17W  
Pawnee County, Kansas  
Company: Honaker Drig., Inc. &  
Colorado Oil & Gas Corp.  
Contractor: Honaker Drig., Inc.


Comm: 9-27-55  
Comp: 10-11-55  
Rotary Total Depth: 4265'  
Casing: 8 5/8" 265'  
5 1/2" 4264'

0	125	Sandy Clay	
125	145	Sand & Gravel	
145	256	Shale & Shells	
256	385	Shale	8 5/8" casing cemented at
385	400	Red Bed & Shale	265' with 175 sacks cement
400	575	Shale & Shells	and 2 sacks calcium chloride
575	685	Sand	
685	1090	Shale & Shells	
1090	1125	Anhydrite	
1125	2000	Shale & Shells	
2000	2540	Lime	
2540	2925	Shale & Lime	
2925	3065	Shale & Shells	5 1/2 casing cemented at
3065	3495	Shale & Lime	4264' with 175 sacks cement
3495	3570	Lime	
3570	3727	Shale & Lime	
3727	4110	Lime	
4110	4185	Conglomerate	
4185	4265	Chert & Lime	
4265		Total Rotary Depth	

I certify that this is the true and correct copy of the above log to the best of my knowledge.

  
H. S. Forbes

Subscribed and sworn to before me this 13th day of October, 1955.

  
Kenneth G. Fischer, Rotary Public

My Commission Expires: 6-25-59