


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 2 Twp. 23 Rge. 17 (47) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW&SW" or footage from lines SW SW SW
Lease Owner Hilton Drilling Company, Inc.
Lease Name Hines Well No. 4
Office Address P. O. Box 108, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 27, 1956
Application for plugging filed March 27, 1956
Application for plugging approved _____ 19____
Plugging commenced March 27, 1956
Plugging completed March 27, 1956
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Brundage
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4290 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 215' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 210' with heavy mud.
Bottom plug at 210' placed with 1/3 sack of hulls and 20 sacks of cement (cemented through drill pipe)
Filled hole to 35' with heavy mud.
Top plug at 35' placed with 1/3 sacks hulls and 10 sacks of cement (cement to bottom of cellar)

3-29-56

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Hilton Drilling Company, Inc.
Address P. O. Box 108 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of March, 19 56

Mildred Hobbie
Notary Public.

My commission expires _____

24-7368-S 3-53-20M

MILDRED HOBBIIE
MY COMMISSION EXPIRES MARCH 6, 1958

PLUGGING
FILE SEC 2 T 23 R 17W
BOOK PAGE 49 LINE 24

DRILLER'S LOG

15-145-01057-0000

COMPANY: Hilton Drilling Company, Inc. LOCATION: SW SW SW
 Sec. 2-23S-17W
 Pawnee County, Kansas
 CONTRACTOR: Hilton Drilling Company, Inc.
 FARM NAME: Hines No. 4 ELEVATION: 2090 D.F.
 COMMENCED: March 13, 1956 Casing Used: 8-5/8" @ 215' w/200 sxs.
 COMPLETED: March 27, 1956

| | |
|-------------------------|------|
| Sand, Clay and Shale | 216 |
| Shale | 340 |
| Shale and Surface Clay | 400 |
| Red Bed | 570 |
| Sand | 650 |
| Shale, Shells & Red Bed | 1115 |
| Anhydrite | 1140 |
| Shale and Shells | 1787 |
| Shale and Lime | 2295 |
| Lime | 2600 |
| Shale and Lime | 3400 |
| Lime | 3712 |
| Shale and Lime | 3796 |
| Lime | 4133 |
| Shale and Lime | 4179 |
| Lime and Chert | 4194 |
| Chert and Shale | 4290 |
| Total Depth | 4290 |

STATE OF KANSAS)
) SS.
 COUNTY OF BARTON)

RECORDED
 CONFIDENTIAL DIVISION

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above-described.

HILTON DRILLING COMPANY, INC.

Henry Peacock
 Henry Peacock, Secretary

Subscribed and sworn to before me this 28th day of March, 1956.

Mildred Hobbie
 Notary Public

MILDRED HOBBIE
 MY COMMISSION EXPIRES MARCH 6, 1958

PLUGGING
 REC'D BY 23 R 17W
 BOOK PAGE 49 LINE 24