

State of Kansas



15.185.11360.0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

11-18-63

Dear Sir:

Mr. Frank Psannenstiel of Garvey Drilling Co. has this
date requested permission to plug the following described well:

Mr. Psannenstiel guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Harter "A" Well No. # 3

Location: SE NW SE Sec. 8 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3628 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Psannenstiel was instructed to plug the well as follows:

327' of 8 5/8" surface pipe, cemented with 400 sacks.
Fill hole with drilling mud to 300', 1st cementing plug,
1/4 sack hulls, cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement
with 10 sacks to base cellar. Bridge and cement rat hole
with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent