



15.185.30080.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

RECEIVED  
SEP 19 1966  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Sept. 13, 1966

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty

Complete Address: 800 Bitting Building Wichita, Kansas

Lease Name: Fisher #1 Well No. #7

Location: SW-NE-NE Sec. 8 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3585' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Glenn was instructed to plug the well as follows:

3577' of 5 1/2" pipe plugged back to 3500'. Perf. at 3330' Sand to 3300' & 5 sacks cement. 294' of 8 5/8" surface pipe circulated with 280 sacks cement. Mud to 290', 10' rock bridge, 4 sacks cement with calcium per haler. Set for 2 1/2 hours. Baled down & 20 sacks cement. Hole filled with mud to 40', 10' rock bridge and 10 sacks cement to base of cellar.

Very truly yours,

Kenneth Gustus  
Conservation Division Agent