



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 7 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts.
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Doyle Rand of Harms Drilling Co. has this

date requested permission to plug the following described well:

Mr. Rand guarantees payment of the plugging fee.

Operator's full Name: Harms Drilling Co. & Nadel & Gussman

Complete Address: Box 488, Great Bend, Kansas

Lease Name: Harms "B" Well No. # 1

Location: SW NW SE Sec. 20 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3726 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rand was instructed to plug the well as follows:

309' of 8 5/8" surface pipe, cemented with 250 sacks.
Fill hole with mud to 180', 1st cementing plug, 1/2 sack
hulls, cement with 20 sacks. Fill hole with mud to 40',
2nd cementing plug, 1/2 sack hulls, cement with 10 sacks
to base cellar. Rat hole bridged and cemented with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent