



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1972
CONSERVATION DIVISION
Wichita, Kansas
12-14-72

Dear Sir:

Mr. Davis of Halliburton has this

date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Halliburton Oil Producing

Complete Address: 117 Cameron Bldg., Oklahoma City, Oklahoma

Lease Name: Frusher Well No. 1

Location: C NE SW Sec. 9 Twp. 21 Rge. 23 (E)(W)

County: Hodgeman Total Depth 2650' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Davis was instructed to plug the well as follows:

8 5/8" to 326' circulated w/ cement. Mud 2650' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 300'

Spot 30 sacks cement 300' to 200' Mud 200' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent