

To: 1 040511  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339

Operator: K & K Oil

Name &

Address P.O. Box 176

Chase, KS 67524

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 13 Month: 2 Year: 19 91

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 3500', Perfs at 3434-38'

1st plug sand back to 3350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and

125 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11 a.m. Day: 13 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3380' and dumped 4 sx cement on top of  
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx-gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 400 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1400' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED  
(If additional description is necessary, use BACK of this form.)

DATE 2-26-91

INV. NO. 30912

2-13

MAY 03 1991

Signed Stephen J. Pfeifer  
(TECHNICIAN)

FORM CP-2/3  
Rev. 01-84

2-13 146  
API NUMBER 15- 185-20,134 .0000  
NW NW NE SEC. 9 T 21 S, R 14 W/E  
4950 feet from S section line  
2310 feet from E section line  
Lease Name Asher "B" Well # 3  
County Stafford 113.81  
Well Total Depth 3502 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 459