

2-12 15.185.00348.0001 145

To: 1 040510
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 2/13/69
SE, NW NE, SEC. 9, T 21 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339

Operator: K & K Oil
Name & Address: P.O. Box 176
Chase, KS 67524

4290 foot from S section line

1650 foot from E section line

Lease Name Asher "B" Well # 1 (OWWO)

County Stafford 118.00

Well Total Depth 3631 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 847

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 12 Month: 2 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2", Perfs at 3436-40'

1st plug pump 1 sx hulls and 25 sx cement,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 12 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped with 50 sx common cement, stopped plug at 1900',

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls and 125 sx cement.

Maximum pressure 600 psi and shut in 100 psi.

Surface pipe plated with collar to pump through.

Note: Holes in surface pipe-waited on welder and backhoe to repair.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.)

DATE 2-26-91

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 30911

2-12 MAY 03 1991