

To: 1 040509
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-12 147
API NUMBER 15- 185-20,122-0000
NE NW NE, SEC. 9, T 21 S, R 14 W/E
4950 feet from S section line
1650 feet from E section line
Lease Name Asher "B" Well # 2
County Stafford 118.00
Well Total Depth 3631 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 454

TECHNICIAN'S PLUGGING REPORT

Operator License # 9339
Operator: K & K Oil
Name & Address P.O. Box 176
Chase, KS 67524

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Stepco Well Service License Number 9764

Address P.O. Box 265, Ellinwood, KS 67526

Company to plug at: Hour: 10 a.m. Day: 12 Month: 2 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) K & K Oil (phone) 316-938-2943

were: 4 1/2" at 3629', Perfs at 3446-51', Bridge in hole at 730'

1st plug pump down 8 5/8" X 4 1/2" annulus through 1" tubing set at 757' with 250 sx cement.

2nd plug pump down 4 1/2" casing through 2 3/8" tubing set at 730' with 125 sx cement.

RECEIVED
STATE OF KANSAS COMMISSION 2-18-91

FEB 18 1991 Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 12 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped down 8 5/8" X 4 1/2" annulus through 1" tubing set
at 757' with 250 sx cement.

2nd plug pumped down 4 1/2" casing through 2 3/8" tubing set at 730' with 125 sx cement.

Cement circulated in 4 1/2" casing and in 8 5/8" X 4 1/2" annulus.

Bridge in hole at 730', unable to get any deeper, 1" hung up in annulus, parted, left
approx. 560' of 1" tubing in hole (annulus). Had communication between 4 1/2" casing
and 8 5/8" X 4 1/2" annulus.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(if additional description is necessary, use BACK of this form.)

INVOICED (do not XXXXX) observe this plugging.

DATE 2-26-91

INV. NO. 30913

2-12

MAY 03 1991

Signed Stephen J. Pfeifer
(TECHNICIAN)