

15.185.00937.0002

TO: 1052236  
STATE CORPORATION COMMISSION

4-1

API NUMBER 15- Drilled 1960  
NW SW NW, SEC. 12, T 21 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4950 FEET FROM East SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME Piel A WELL # 3

TECHNICIAN'S PLUGGING REPORT COUNTY Stafford 140.17

OPERATOR LICENSE # 30517 WELL TOTAL DEPTH 4313 FEET

OPERATOR: TURNCO DRILLING INC. PRODUCTION CSG: SIZE 5 1/2" FEET 3749'

NAME AND 3900 BROADWAY SURFACE CASING: SIZE 8 5/8" FEET 296'

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL      GAS WELL      INPUT WELL      SWD WELL D-11750 D/A     

OTHER WELL AS HEREINAFTER INDICATED     

PLUGGING CONTRACTOR MIKES TESTING AND SALVAGE INC. LICENSE NUMBER 31529

ADDRESS P. O. BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 1 MONTH: APRIL YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKES TESTING AND SALVAGE INC. (PHONE) 316-938-2943

WERE: PERFORATIONS 3667-77 OPEN HOLE 3749-4313 PBTD 3700

SAND BOTTOM TO 3610' AND PLACE 5 SX OF CEMENT ON TOP OF SAND WITH A DUMP BAILER.

SPOT PLUGS THROUGH CASING WHILE COMING OUT OF HOLE WITH PIPE. 1ST PLUG AT 800' WITH 10 SX

OF GEL AND 50 SX OF CEMENT. 2ND PLUG AT 330' WITH 50 SX OF CEMENT. 3RD PLUG AT 40' WITH

10 SX OF CEMENT TO SURFACE. RECOMMENDED 60/40 POZMIX 6% GEL FOR CEMENT

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART      NONE     

OPERATIONS COMPLETED: HOUR: 2:00 PM DAY: 1 MONTH: APRIL YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3572 AND PLACED 5 SX OF CEMENT ON TOP OF SAND

SPOTTED PLUGS THROUGH CASING WHILE PULLING PIPE

1ST PLUG AT 790' WITH 9 SX OF GEL FOLLOWED BY 50 SX OF CEMENT

2ND PLUG AT 310' WITH 50 SX OF CEMENT

3RD PLUG AT 40' WITH 10 SX OF CEMENT CIRCULATING CEMENT TO SURFACE.

FAIR CIRCULATION THROUGH OUT JOB

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED RECOVERED 1820' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey  
(TECHNICIAN) FORM CP-2/3

DATE 4-15-98

INV. NO. 50363

4-8-98

*[Handwritten signature]*