

052098

12-31

API NUMBER 15-Drill completion date 10/16/59

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SW-NE NW, SEC. 12, T 21 S, R 14 W/EX
4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30517

Lease Name Piel Well # 2

Operator: Turnco Drilling, Inc.
Name & Address
3900 Broadway
Great Bend, KS 67530

County Stafford 118.65
Well Total Depth 3651 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 31 Month: 12 Year: 19 96

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3649'; Open hole 3649-51', Squeezed at 600' w/200 sx cement
1st plug sand back to 3600' and dump 5 sx cement on top of sand through bailer,
2nd plug run tubing to 850' and load hole, circulate with cement to surface.

1-6-97

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:20 a.m. Day: 31 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 5 sx cement on top of sand through bailer,

2nd plug ran tubing to 847', loaded hole and circulated with 75 sx cement,

3rd plug pumped another 75 sx cement down 5 1/2",

4th plug hooked onto 8 5/8", pumped 15 sx cement and blew hole in surface pipe.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (Name) observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

DATE JAN 08 1997

INV. NO. 47285