

1 080390

R

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- D&amp;C 12-10-59

NW SE NW, SEC. 12, T 21 S, R 14 W/8

3630 feet from S section line

3630 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5816

Lease Name Piel Well # 4

Operator: Gulf Oil Corporation

County Stafford 119.54

Name &amp;

Address P. O. Box 12116

Well Total Depth 3678 feet

Oklahoma City, OK 73157

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kincaid Well Service, Inc. License Number 7252

Address P. O. Box 276, Ellinwood, KS 67526

Company to plug at: Hour: 9:00 am Day: 11 Month: June Year: 19 85

Plugging proposal received from Paul Yowell

(company name) Gulf (phone) 405-949-7000

were: 5 1/2" at 3673' Perfs at Arbuckle

1st plug pump 50# hulls and 50 sx cement to bottom

Spot cement through 5 1/2" casing with mud between plugs

2nd plug at 830' with 20 sx cement

3rd plug at 330' with 20 sx cement

Orders given by Richard W. Lacey

4th plug at 90' with 10 sx. Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:30 am Day: 12 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug spotted 50 sx cement at 3678'. Tagged cement at 3245'

Spotted 25 sx gel at 3240. Spotted 20 sx cement at 885'. Spotted mud at 709'. Spotted  
20 sx cement at 340'. Spotted mud at 188'. Spotted 9 sx cement at 93'. Cement circulated.

Tried to pump into backside. Pressured up to 1500 psi and could not pump into backside.

6-12-85 Cut 5 1/2" &amp; 8 5/8" off. Ran 1" to 175' Tagged cement. Spotted 30 sx cement at

165'. Cement circulated. This well had been squeezed at 1080' with 200 sx cement.

Remarks: No recovery. Used Class H cement by Dowell.

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this form.)

(old / 1000000) observe this plugging.

DATE 6-24-85

Signed

INV. NO. 8672

JUL 1 8 1985