

.1052312

TO: STATE CORPORATION COMMISSION

4-22

API NUMBER 15-185-20,396.0000
SE SW SW SEC. 12, T 21 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BLAKESLEE WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 119.96

OPERATOR LICENSE # 6170

WELL TOTAL DEPTH 3691 FEET

OPERATOR: GLOBE OPERATING, INC

PRODUCTION CSG: SIZE 5 1/2" @ 3690' WITH 150 SX

NAME AND PO BOX 12

SURFACE CASING: SIZE 8 5/8" @ 286' WITH 250 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 22 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3617-20

SANDED TO 3540' AND 5 SX CEMENT.

PUMP DOWN 8 5/8" WITH 400# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" WIPER PLUG - 100 SX CEMENT. MAXIMUM PRESSURE 300. SHUT IN PRESSURE 200.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:45 PM DAY: 22 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED TO 3540' AND 5 SX CEMENT.

PUMP DOWN 8 5/8" WITH 400# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" WIPER PLUG - 100 SX CEMENT. MAXIMUM PRESSURE AT 300. SHUT IN PRESSURE AT 200.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1910' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

RECEIVED

I (DID) OBSERVE THIS PLUGGING OPERATION OF THE STATE CORPORATION COMMISSION

SIGNED Richard M. Lacey (TECHNICIAN)

Handwritten initials

DATE APR 29 1999

APR 26 1999

FORM CP-2/3

INV. NO. 60896

4-26-99

CONSERVATION DIVISION
Wichita, Kansas