

1 050224

15.055.00180.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE SE NW, SEC. 14, T 21 S, R 33
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 3-28-61
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6814

Lease Name Stover Well # 1-14

Operator: Cargill, Inc.
Name & Address Suite 604, One Main Place
Wichita, KS 67202

County Finney

Well Total Depth 2655 86.29 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 7" / _____ feet 340

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 17 Month: May Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso Casing Pulling (phone) 316-938-2348

were: 4 1/2" set at 2655' Perfs 2581 - 85'

1st plug sand back to 2530' and dump 4 sx cement on top of sand.

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and release 7" rubber plug and pump an additional 225 sx cement.

Plugging Proposal Received by Richard W. Lucy
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:00 am Day: 17 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 2655' Perfs 2581 - 85'

1st plug sanded back to 2530' and dumped 4 sx cement on top of sand.

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 7" rubber plug, and pump an additional 225 sx cement.

Maximum pressure 500# and shut in pressure 100#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied. They recovered 1300' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-25-84

INV. NO. 1654

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1984

Signed Richard W. Lucy
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas