

10-28-87

1 061031

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,550.0000
70' N C S/2
SE NE, SEC. 7, T 21 S, R 33 W/8X
3040 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Buerkle Well # 1

Operator: Mustang Drilling & Exploration
Name &

County Finney 156.65

Address P.O. Box 1609

Well Total Depth 4820 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exploration License Number 5652

Address P.O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 28 Month: 10 Year: 19 87

Plugging proposal received from Jim Meroney

(company name) Mustang Drilling & Exploration (phone) 316-792-7323

were: 5 1/2" at 4754' Perfs at 4568-72' DV'd at 2054' w/400 sx cement Elevation 2921' GL

1st plug pump 2 sx hulls and 25 sx cement on bottom.

2nd plug at 2070' with 25 sx cement,

3rd plug at 455' with 25 sx cement,

4th plug at 40-0' with 4 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 28 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 4607' with 2 sx hulls and 25 sx cement on bottom,

filled hole with gel between plugs.

2nd plug at 2070' with 25 sx cement,

3rd plug at 455' with 25 sx cement,

4th plug at 40-0' with 4 sx cement.

8 5/8" pressured up to 1400 psi immediately.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No recovery.
(if additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 11-12-87

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 18834

RECEIVED
STATE CORPORATION COMMISSION
NOV 2 1987
CONSERVATION DIVISION
Wichita, Kansas