

To: 1 070398
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NW NW NE, SEC. 29, T 21 S, R 22 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-25-87
API NUMBER 15-083-21,283-0000
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3248

Lease Name Alison #1 Well # 2-2

Operator: Masters Operating Company
Name & Address P.O. Box 3356
Wichita, KS 67202

County Hodgeman 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 6:45 p.m. Day: 25 Month: 8 Year: 19 87

Plugging proposal received from Dana Gramly

(company name) Red Tiger Drilling Company (phone) 316-263-1201

were: to fill hole with mud and spot cement through drill pipe Elevation 2266'
Anhydrite 1442-76'

1st plug at 1500' with 50 sx cement, 2nd plug at 850' with 50 sx cement,
3rd plug at 480' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 8:30 p.m. Day: 25 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1475' with 50 sx cement,

2nd plug at 650' with 60 sx cement,
3rd plug at 460' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 10 sx cement.

8-31-87

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED
(do not XXXXXX) conserve this plugging.

DATE 9-3-87

Signed Dan Gordon (TECHNICIAN)

INV. NO. 18003

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. 8 15 87
month day year

API Number 15-083-21,283-0000

OPERATOR: License 3248
Name: Masters Operating Company
Address: P.O. Box 3356
City/State/Zip: Wichita, Kansas 67202
Contact Person: Bob Stozle
Phone: 316-945-9123

C NW NW NE 29 Twp 21 S, Rg 22W X East
4950 Ft. from South Line of Section
2310 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearst lease or unit boundary line 330 feet
County: Hodgeman

CONTRACTOR: License 5302
Name: Red Tiger Drilling Co.
City/State: Wichita, Kansas 67202

Lease Name: Alison #1 Well # 12-2
Ground surface elevation 2266 feet MSL
Domestic well within 330 feet: —yes X no
Municipal well within one mile: —yes X no

Well Drilled For: Well Class: Type Equipment:
X Oil — Storage — Infield X Mud Rotary
— Gas — Inj — Pool Ext. — Air Rotary
— OWWO — Expl — Wildcat — Cable

Depth to bottom of fresh water:
Depth to bottom of usable water: 400
Surface pipe by Alternate: 400 420 1 X 2
Surface pipe planned to be set:
Conductor pipe required: N/A
Projected Total Depth: 4500 feet
Formation: Miss

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., with plugging to KCC
Date 8-13-87 Signature of Operator or Agent: *George A. Oyle* Owner
BY RED TIGER DRILLING CO.

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 420 feet per Alt 1 X
This Authorization Expires 2-13-88 Approved By *Feb. 8-13-87*

*SPUD. 8-15-87
420' 8/8/87
Steve*

NW NW NE.. Sec. 29 Twp. 21 S. Rg. 22W X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep	B. Anhy	or formation with	50 SX	feet of	60-40 poz., 6% gel
2nd plug @ ft. deep	B. Dakota	or formation with	80 SX	feet of	
3rd plug @ ft. deep	430'	or formation with	50 SX	feet of	
4th plug @ ft. deep	40'	or formation with	10 SX	feet of	
5th plug @ ft. deep		or formation with		feet of	
(2) Rathole to surface minus 5 feet	15 BX				(b) Mousehole to surface minus 5 feet

PUSHER *Dana Gramly*
TD *4550'* FORMATION *MISS.*
SURFACE PIPE *8 5/8" @ 429'*
ANHYDRITE *1476'* ELEVATION *2266'*
STARTING TIME & DATE *6:45 PM*
COMPLETION TIME & DATE *8:30 PM*
1st PLUG @ *1475 FT. W/ 50 SX*
2nd PLUG @ *650 FT. W/ 60 SX*
3rd PLUG @ *460 FT. W/ 40 SX*
4th PLUG @ *40 FT. W/ 10 SX*
6440 lbs. 6% 2% cc
RAT HOLE CIRCULATED W/ *10 SX*
MOUSE HOLE CIRCULATED W/ *SX*
WATER WELL PLUGGED W/ *SX*
CEMENT COMPANY *Allied*
TECHNICIAN *Dan Goodrow, Saw Part*

AUG 31 1987
Wichita, Kansas