

To: 1 070515
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-24-88 153 R
API NUMBER 15- 083-21,299.0000

NW NW SW, SEC. 26, T 21 S, R 23 W/8
2310 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3447

Lease Name Holmes Well # 1-26

Operator: Ranken Energy Corporation
Name & Address 2932 N.W. 122nd, Suite 18
Oklahoma City, OK 73120

County Hodgeman 151.78

Well Total Depth 4670 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor R & C Drilling Company License Number 9087

Address P.O. Box 296, Hays, KS 67601

Company to plug at: Hour: 10:30 p.m. Day: 23 Month: 2 Year: 19 88

Plugging proposal received from John Wise

(company name) R & C Drilling Company (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1564-86'
Elevation 2343'

1st plug at 1590' with 50 sx cement, 2nd plug at 850' with 50 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2:30 a.m. Day: 24 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement, 2nd plug at 850' with 50 sx

cement, 3rd plug at 390' with 40 sx cement,

4th plug at 230' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1988 2-26-88

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 2-29-88

Signed Dan Goodrow
(TECHNICIAN)

INV. NO. 19951

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

CARD MUST BE SIGNED

Expected Spud Date. Feb. 5, 1988
month day year

API Number 15-083-21, 299.00002

OPERATOR: License # 3447
Name Ranken Energy Corporation
Address 2932 N.W. 122nd, Ste. 18
City/State/Zip Okla. City, OK 73120
Contact Person Gary Misak
Phone (316) 792-3664

CONTRACTOR: License # 9087
Name R. & C. Drilling Co.
City/State Hays, Kansas

Well Drilled For: Well Class: Type Equipment:
☒ Oil ☐ Storage ☐ Infield ☒ Mud Rotary
☐ Gas ☐ Inj ☐ Pool Ext. ☐ Air Rotary
☐ OWWO ☐ Expl ☒ Wildcat ☐ Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 1/8/88 Signature of Operator or Agent Title President

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt.
This Authorization Expires 7-13-88 Approved By RCH 1-13-88

NW/4NW/4SW/4 Sec 26 Twp 21 S, Rg 23
2310' Ft. from South Line of Section
4950' Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 330' feet
County Hodgeman
Lease Name Holmes Well # 1-26
Ground surface elevation 2343 feet MSL
Domestic well within 330 feet: yes ☒ no
Municipal well within one mile: yes ☒ no
Depth to bottom of fresh water 100'
Depth to bottom of usable water 420' 480'
Surface pipe by Alternate: 1-2
Surface pipe planned to be set 200'
Conductor pipe required
Projected Total Depth 4650' feet
Formation Mississippian

EFFECTIVE DATE: 1-18-88

2-16-88

8 5/8" @ 200'

NO - w. w.

NW/4NW/4SW/4 Sec. 26 Twp. 21 S, Rg. 23 East ☒ West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep. Base Anhydrite or formation with 50. SXS feet of. 60-40. Poz. w/6% gel
2nd plug @ ft. deep. Cheyenne or formation with 80. SXS feet of. " " " " " "
3rd plug @ ft. deep 30' Below Base surface pipe or formation with 40. SXS feet of. " " " " " "
4th plug @ ft. deep 40' From Surface or formation with 10. SXS feet of. " " " " " "
5th plug @ ft. deep or formation with feet of. " " " " " "

(2) Rathole to surface minus 5 feet 15 SXS (b) Mousehole to surface minus 5 feet 15 SXS

NOTE: Agreement between

PUSHER John Wise
TD 4670 FORMATION
SURFACE PIPE 8 5/8" @ 215'
ANHYDRITE 1564' ELEVATION 2343
STARTING TIME & DATE 10:30 2-23-88 PM
COMPLETION TIME & DATE 2:30 2-24-88
1st PLUG @ 1590 FT. W/ 50 SX
2nd PLUG @ 850 FT. W/ 50 SX
3rd PLUG @ 390 FT. W/ 40 SX
4th PLUG @ 230 FT. W/ 40 SX
5th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 60/40 6% SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY B J TITAN
TECHNICIAN D.G.

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1988
CONSERVATION DIVISION
Wichita, Kansas

Off - Set Land owned
w. w. @ 320'
Put additional plug @ to
cover w. w. in interval. SQ