

To: 1 120066
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3447

Operator: Ranken Energy Corporation
Name & Address: 2932 N.W. 122nd, Suite 18
Oklahoma City, OK 73120

2-14-88 99
API NUMBER 15-083-21,301-0000
SE SW NE, SEC. 26, T 21 S, R 23 W/E
2890 feet from S section line
1920 feet from E section line

Lease Name Bamberger Well # 1

County Hodgeman 150.31

Well Total Depth 4625 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 222

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R & C Drilling Company License Number 9087

Address PO Box 296, Hays, KS 67601

Company to plug at: Hour: 11:30 a.m. Day: 14 Month: 2 Year: 19 88

Plugging proposal received from John Wise

(company name) R & C Drilling Company (phone) 913-625-4548

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2291'
Anhydrite 1518-40'

1st plug at 1540' with 50 sx cement, 2nd plug at 770' with 80 sx cement,
3rd plug at 260' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 p.m. Day: 14 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1540' with 50 sx cement,

2nd plug at 770' with 80 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Howco.

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to observe this plugging.

DATE 2-22-88

V. NO. 19900

MAR 24 1988

Signed Duane Rankin
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
2-17-88 FEB 17 1988
CONSERVATION DIVISION
Wichita, Kansas

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... February 15, 1988
 month day year

API Number 15- 083-21,301-0000

OPERATOR: License # 3447
 Name Ranken Energy Corporation
 Address 2932 N.W. 122nd, Suite #18
 City/State/Zip Oklahoma City, OK 73120
 Contact Person Gary Misak
 Phone (316) 792-3664

250' FSL NE/4 & 720' FWL NE/4 Sec. 26, Twp. 21 S, Rg. 23
 2890' Ft. from South Line of Section
 1920' Ft. from East Line of Section
 (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 9087
 Name R. & C. Drilling Company No. 296
 City/State Hays, Kansas 67601

Nearest lease or unit boundary line 410' feet
 County Hodgeman
 Lease Name Bamberger Well # 1
 Ground surface elevation 2291' feet MSL
 Domestic well within 330 feet: yes X no
 Municipal well within one mile: yes X no
 Depth to bottom of fresh water 100'
 Depth to bottom of usable water 420' 480'
 Surface pipe by Alternate: 1-2 X
 Surface pipe planned to be set 200'
 Conductor pipe required
 Projected Total Depth 600' feet
 Formation Mississippian

Well Drilled For: Well Class: Type Equipment:
 X Oil Storage Infield X Mud Rotary
 Gas Inj' Pool Ext. Air Rotary
 OWWO X Expl X Wildcat Cable

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
 Date 1-12-87 Signature of Operator or Agent Title President

For KCC Use:
 Conductor Pipe Required feet Minimum Surface Pipe Required 200 feet per Alt. X
 This Authorization Expires 7-22-88 Approved By 1-22-88

EFFECTIVE DATE: 1-27-88
 set 200' of 8 3/8 on 2-5-88

250' FSL NE/4 & 720' FWL NE/4 Sec. 26, Twp. 21 S, Rg. 23 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep	Base Anhydrite	or formation with	50 SXS	feet of	60-40 Poz. w/6% gel
2nd plug @ ft. deep	Cheyenne	or formation with	80 SXS	feet of	" " " " " "
3rd plug @ ft. deep	30' Below Base of surface pipe	or formation with	40 SXS	feet of	" " " " " "
4th plug @ ft. deep	40' From Surface	or formation with	10 SXS	feet of	" " " " " "
5th plug @ ft. deep		or formation with		feet of	
(2) Rathole to surface minus 5 feet					(b) Mousehole to surface minus 5 feet

NOTE: 15 SXS

PUSHER	John Wise	FORMATION	MISS.
SURFACE PIPE	8 3/8 @ 222'	ANEHYDRITE	1518 1/8 ELEVATION 2291
STARTING TIME & DATE	11:30 A.M.	COMPLETION TIME & DATE	2:30 P.M.
1st PLUG @	1540 FT. W/ 50 SX	2nd PLUG @	1770 FT. W/ 80 SX
3rd PLUG @	260 FT. W/ 40 SX	4th PLUG @	40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/	15 SX	MOUSE HOLE CIRCULATED W/	15 SX
WATER WELL PLUGGED W/		CEMENT COMPANY	Howco
TECHNICIAN	Rankin		60-40 Poz 690

STAT. CO. REGISTRATION DIVISION
 WICHITA, KANSAS
 7 1988
 off-site
 690-40 Poz has well @ 380'
 Report to
 Conversion