

1 050535

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,173-0000
C SW SW, SEC. 26, T 21 S, R 23 (W/E)

660 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Holmes Well # 1

Operator: Falcon Exploration, Inc.
Name & Address: 1531 Kansas State Bank Building
Wichita, KS 67202

County Hodgeman 149.86

Well Total Depth 4611 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 466

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hembree Well Service License Number 6907

Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 9:00 am Day: 30 Month: May Year: 19 85

Plugging proposal received from Zack Lewis

(company name) Falcon Exploration (phone) 316-262-1378

were: 4 1/2" at 4610' PBSD 4580' Perfs at 4558-62'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 11:30 am Day: 30 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 175 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 1300 psi and shut in 600 psi

JUN 03 1985

Remarks: Recovered 2506' 4 1/2" casing. Used 60/40 Pozmix 2% gel. CONSERVATION DIVISION BURTON (If additional description is necessary, use BACK of Form 84)

INVOICED

DATE 6-6-85

Signed Richard W. Hoady (TECHNICIAN)

INV. NO. 8341 JUL 12 1985