

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-159-20945.0000

NEWSW, Sec. 15, T 21 S, R 8 W

2310 feet from W section line

990 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Diamond Well # 1

Operator: Hummon Corporation  
Name & Address 400 One Main Place  
Wichita, Kansas 67202

County Rice

Well Total Depth 3430 feet

Conductor Pipe: Size          feet

Surface Casing: Size 8 3/4 feet 267

Abandoned Oil Well          Gas Well X Input Well          SWD Well          D&A         

Other well as hereinafter indicated         

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 10:00 AM Day: 30 Month: 1 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Jim Ray

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Squeeze bottom with 50 sacks common cement stop plug @ 3100'

Squeeze with 125 sacks 50/50 Pozmix w/4% gel + 3% cc.

Signed [Signature]  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part          None         

Operations Completed: Hour: 1:00 PM Day: 21 Month: 3 Year: 1984

ACTUAL PLUGGING REPORT Bottom squeezed with 50 sacks common cement. Plug  
stopped at 3212'. Pipe shot @ 2847' and gas blew in around 2000'.

Pumped 100 sacks Bentonite and killed gas. Pulled casing. Top of  
gel @ 950'. Pumped 15 sacks gel and 125 sacks 50/50 Pozmix  
w/4% gel + 3% cc. Max pressure 550 PSI. closed in @ 550 PSI

Remarks: 4 1/2" - 3419' - 125 sacks. Perfs 3308-12' 4 1/2". 2847' of 4 1/2" casing recovered.  
Allied Cementing Co., Inc. Ticket # 32532

RECEIVED  
STATE CORPORATION COMMISSION

APR 03 1984

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did) ~~did not~~ observe this plugging.

Signed [Signature]  
(TECHNICIAN)

FORM CP-2/3 RPW  
Rev. 9-82  
ML

INVOICED

DATE 4-3-84

INV. NO. 1016