

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20085-00-01
Spot: CSWNW Sec/Twnshp/Rge: 28-21S-33W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: FINNUP Well Number: 2
County: FINNEY Total Vertical Depth: 2750 feet

Operator License No.: 32281
Op Name: GMX RESOURCES, INC.
Address: 9400 N. BROADWAY STE 600
OKLAHOMA CITY, OK 73114

Conductor Pipe: Size _____ feet:
Surface Casing: Size 10.75 feet: 814
Production: Size 4.5 feet: 2744 WITH 1500 SX CMT
Liner: Size _____ feet: 89.38

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/23/2001 12:15 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: HAROLD WRIGHT Company: GMX RESOURCES Phone: (405) 600-0711

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 400# HULLS. CMT TO SURFACE. BRING 50 SX CMT FOR BACKSIDE. TEST TO 500#.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/23/2001 1:45 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2712'. PERFS AT 2542-2674'. PUMPED DOWN 4 1/2" CASING 175 SX CMT. WELL ON VACUUM. PUMPED DOWN 10 3/4" X 4 1/2" 10 SX CMT. PRESSURED UP TO 300#. SHUT IN WITH 300#. TOPPED OFF 4 1/2" WITH 10 SX CMT.

INVOICED
DATE 4-27-01
2001061729

RECEIVED
STATE CORPORATION COMMISSION

APR 27 2001

CONSERVATION DIVISION

Wichita, Kansas

4-27-01

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D Strube

(TECHNICIAN)

APR 26 2001

Form 6-2-01

MP

[Signature]